

North Yorkshire Council

A59 KEX GILL DIVERSION

A59 Kex Gill Culvert (STR005) - Approval in Principle





North Yorkshire Council

A59 KEX GILL DIVERSION

A59 Kex Gill Culvert (STR005) – Approval in Principle

PUBLIC | WSP

PROJECT NO. 70049554 OUR REF NO. A59 KEX GILL CULVERT (STR005)

DATE: OCTOBER 2019

vsp

North Yorkshire Council

A59 KEX GILL DIVERSION

A59 Kex Gill Culvert (STR005) - Approval in Principle

WSP

Mount View Standard Way Business Park Northallerton DL6 2YD

WSP.com

wsp

QUALITY CONTROL

Issue/revision	P01	P02	P03	P04
Remarks	Issued for comments	Final for endorsement	Reissued for value engineering	
Date	3 rd October 2019	25 th October 2019	27 th March 2023	
Prepared by				
Signature				
Checked by				
Signature				
Authorised by				
Signature				
Project number	70049554			
Report number	NYKGDD-WSP-SMN-STR005-RE-CB-0001			
File reference	NYKGDD-WSP-SMN-STR005-RE-CB-0001_P03			

vsp

CONTENTS

1.	HIGHWAYS DETAILS	1
2.	SITE DETAILS	2
3.	PROPOSED STRUCTURE	3
4.	DESIGN CRITERIA	10
5.	STRUCTURAL ANALYSIS	13
6.	GEOTECHNICAL CONDITIONS	15
7.	CHECK	17
8.	DRAWINGS AND DOCUMENTS	18
9.	THE ABOVE IS SUBMITTED FOR ACCEPTANCE	19
10.	THE ABOVE IS REJECTED/AGREED SUBJECT TO THE AMENDMENTS AND CONDITIONS SHOWN BELOW	20

APPENDICES

APPENDIX A LIST OF RELEVANT DOCUMENTS FROM THE TAS APPENDIX B LOCATION PLAN APPENDIX C PROPOSED GENERAL ARRANGEMENT DRAWINGS APPENDIX D IDEALISED DIAGRAM APPENDIX E

wsp

DESIGNERS RISK ASSESSMENT APPENDIX F CULVERTS FEASIBILITY STUDY APPENDIX G TAA CORRESPONDENCE

APPENDIX A

LIST OF RELEVANT DOCUMENTS FROM THE TAS

APPENDIX B

LOCATION PLAN

APPENDIX C

PROPOSED GENERAL ARRANGEMENT DRAWINGS

APPENDIX D

IDEALISED DIAGRAM

APPENDIX E

DESIGNERS RISK ASSESSMENT

APPENDIX F

CULVERTS FEASIBILITY STUDY

APPENDIX G

TAA CORRESPONDENCE

vsp

INTRODUCTION

The A59 provides a key strategic east-west connection in North Yorkshire, linking Harrogate and Skipton. There is a long history of landslips around this location. These landslips deposit material onto the road leading to unpredictable closures of the A59. Analysis of existing geotechnical information indicates that the primary cause of these landslips is heavy rainfall, coupled with relatively unstable land on the hillside slopes, leading to earthwork failures.

Various studies, site investigations, consultation events and the production of reports, such as the Option Appraisal Report, have resulted in the determination of the preferred new A59 road realignment. A detailed design of this preferred realignment is now being developed.

To accommodate the proposed A59 alignment, 8 new culverts shall be required. The new culverts will be used to carry existing watercourses beneath the proposed A59 road. This AIP document, prepared in accordance with BD2/12 Technical Approval of Highway Bridges, relates to the design of the new A59 Kex Gill Culvert (STR005) on the A59 Kex Gill diversion road (CH4085).

1. HIGHWAYS DETAILS

1.1. TYPE OF HIGHWAY

The proposed A59 diversion at the location of the proposed culvert (CH4085) is a rural single all-purpose carriageway road (WS2) in accordance with TD27/05 with the following features:

- Eastbound/Westbound hardstrip = 1.0m
- Eastbound lane (downhill lane) = 3.4m
- Westbound lane (uphill lane 1) = 3.2m
- Westbound lane (uphill lane 2) = 3.4m
- Eastbound/Westbound verge = 2.5m

A 3.0m wide bridleway and 1.0m verges cross over the culvert at the southern end.

1.2. PERMITTED TRAFFIC SPEED

A59 section over structure – 60mph (96kph).

1.3. EXISTING RESTRICTIONS

Not Applicable.

2. SITE DETAILS

2.1. OBSTACLE CROSSED

The proposed A59 Kex Gill Culvert (STR005) carries the Hall Beck watercourse beneath the proposed A59 diversion alignment at CH4085, refer to location plan in Appendix B.

3. PROPOSED STRUCTURE

3.1. DESCRIPTION OF STRUCTURE AND DESIGN WORKING LIFE

The proposed structure covered by this AIP includes:

• A59 Kex Gill Culvert (STR005)

The culvert shall comprise a precast concrete box structure together with precast concrete headwalls & wingwalls at each end.

A mortared stone wall (with locally sourced stonework and recessed joints to give the appearance of a drystone wall) shall be installed along the top of the headwalls and wingwalls at each end of the culvert. This is to prevent pedestrian falls from height into the watercourse during inspection and maintenance-based activities.

To satisfy heritage requirements, consideration shall be given to facing the culvert entrances, headwalls & wingwalls with locally sourced stone blockwork. This natural stone face finish will enhance the aesthetic appearance of the structure and the integration with the surrounding rural environment. Refer to Appendix C for general arrangement of the proposed culvert.

In accordance with Table A.1 of BD100/16, the design working life of the structure will be 120 years (Category 5). Replacement structural parts will have a design working life of up to 50 years (Category 2).

3.2. STRUCTURAL TYPE

The proposed structure is a single span precast concrete box culvert with precast concrete headwalls & wingwalls.

The wingwalls shall comprise freestanding cantilever type walls acting independently of the box culvert.

3.3. FOUNDATION TYPE

Spread footing foundations shall be provided for the precast box and wingwalls.

3.4. SPAN ARRANGEMENTS

The single span culvert shall comprise the following internal dimension:1.0m wide by 1.4m high. The invert of the structure shall comprise a 300mm thick natural bed formation.

The approximate total length of the structure shall be 40.6m. The wingwalls shall be splayed with height/lengths to suit final embankment slope profiles.

3

3.5. ARTICULATION ARRANGEMENTS

The box culvert shall be formed from multiple precast concrete segments of a prescribed length positioned end to end. There will be interlocking joints (with Tok strip sealant) between each segment. The wingwalls shall be independent of the box culvert and separated by a vertical joint comprising expanded closed cell polyurethane joint filler with a polysulphide sealant.

The structure shall run in the NE – SW direction (following alignment of the existing Hall Beck) with a skew angle of approximately 10° to the proposed A59 road alignment.

3.6. CLASSES AND LEVELS

3.6.1 CONSEQUENCE CLASS

The whole structure shall be consequence class CC2 in accordance with Table A.2 of BD100/16.

3.6.2 RELIABILITY CLASS

The whole structure shall be reliability class RC2 in accordance with Table A.2 of BD100/16.

3.6.3 INSPECTION LEVEL

The structure shall have an Inspection Level IL2 in accordance with Table A.2 of BD100/16.

3.7. ROAD RESTRAINT SYSTEMS REQUIREMENTS

A VRS with containment class N2 will be provided to the verges of the proposed A59 road alignment.

A mortared stone wall (with locally sourced stonework and recessed joints to give the appearance of a drystone wall) shall be installed along the top headwalls and wingwalls at each end of the culvert. This is to prevent pedestrian falls from height into the watercourse during inspection and maintenance-based activities.

3.8. PROPOSED ARRANGEMENTS FOR FUTURE MAINTENANCE AND INSPECTION

3.8.1 TRAFFIC MANAGEMENT

It is unlikely traffic management will be required to access the culvert structure during maintenance/inspection activities since both ends of the culvert are set back away from the carriageway.

Where traffic management is necessary then it will take the form of temporary single lane closure of the A59 carriageway.

3.8.2 ARRANGEMENTS FOR FUTURE MAINTENANCE AND INSPECTION OF STRUCTURE. ACCESS ARRANGEMENTS TO STRUCTURE

Maintenance/inspection activities to the proposed culvert may be carried out on foot.

The upstream headwall and wingwalls may be accessed from behind the VRS on the proposed A59 eastbound carriageway. Where the VRS terminates, the adjacent verge will be locally widened to accommodate parking for maintenance personnel. The downstream headwall and wingwalls may be accessed via the bridleway access track. Access to inside of the culvert shall only be possible when water levels are sufficiently low.

The structure will be classified as a confined space with a suitable safe system of work expected to be in place during inspection and maintenance work.

3.9. ENVIRONMENT AND SUSTAINABILITY

Prior to construction, a construction environment management plan (CEMP) will be produced detailing methods to minimise the impact of the proposed structure. The CEMP will contain the following information (but not limited to):

- Careful planning of the construction sequence in consultation of hydraulic/drainage engineers to minimise disruption to the existing Hall Beck watercourse.
- Strategy to control construction noise, vibration, lighting and egress of mud and dust.
- A plan to prevent discharge of contaminated drainage into groundwater.
- Facilities for the storage of oils, fuels or chemicals.
- Methods to minimise waste and re-use onsite materials within requirements of the specification and use of materials which can be ultimately recycled.

To reduce environmental impact and improve sustainability, a precast concrete box culvert has been proposed to reduce the amount of on-site works and speed up construction.

An Ecology survey conducted by WSP on 22nd/23rd May 2019, confirmed no requirements to provide any additional ecological features within the proposed structure (mammal ledges, fish baffles etc.).

To satisfy heritage requirements, consideration shall be given to facing the concrete headwalls/wingwalls with locally sourced stone blockwork. This natural stone face finish will enhance the aesthetic appearance of the structure and the integration with the surrounding rural environment.

3.10. DURABILITY, MATERIALS AND FINISHES

3.10.1 MATERIALS

Refer to the table below for material information:

TABLE 1: Material Information		
Proposed A59 Kex Gill Culvert (STR005)		
Structural Concrete: Precast Box Culvert, Headwalls & Wingwalls	Minimum strength Class C40/50 (in accordance with series 1700 of MCHW)	
Blinding Concrete	FND2 designated concrete in accordance with BS 8500-1:2015+A2:2019.	
Steel Reinforcement	Grade 500B to BS4449:2005	
Waterproofing	A permitted waterproofing system (in accordance with series 2000 of the MCHW) shall be used on the top outer surface of the box culverts and be continued down the outside of the abutment to a level 200 mm below the soffit.	
	All structure external buried surfaces (including the base) not protected by a permitted waterproofing shall be coated with two coats of bituminous paint (in accordance with series 2000 of MCHW) for below ground concrete structures.	
Safety Barrier (at A59 verge level)	N2 containment steel safety barrier	
Structural Backfill	Class 6N/6P (in accordance with series 600 of MCHW) Minimum effective angle of friction ϕ ' = 35°, and effective cohesion c' = 0.	
Stone Wall Facing	Locally sourced gritstone blockwork.	
Stone wall (to topside of headwalls & wingwalls)	Specification requirements shall be confirmed during detail design.	
Mortar for stonework	It is anticipated the mortared joints shall be high durability i.e. 1 part cement: 0.5 part lime: 4.5 parts sand: M6 designation mortar class (ii) to BS EN 1996- 1-1:2005+A1:2012 modified by the UK National Annex and BS 5628 part 1. A proportion of sharp sand shall also be included.	

3.10.2 EXPOSURE CLASSES FOR REINFORCED CONCRETE

All concrete exposure class designations shall be in accordance with BS 8500-1 and BS EN 206-1, see table below. The class designations ignore conservatively ignore surface protection provided by stone facing etc.

TABLE 2: Concrete Exposure Classes				
Concrete Surface	XC	XD	XF	Comment(s)
All internal faces of the box culvert	XC3/4	XD2	XF1	 Concrete surfaces sheltered from, or exposed to, direct rain. Concrete surfaces exposed to alternate wetting and drying. Concrete surfaces not subject to de-icing salts.
Buried faces of box culvert, headwalls & wingwalls less than 1m below carriageway level	XC2	XD3	XF2	 Concrete buried in non-aggressive soil. Concrete surfaces exposed to de-icing salts directly/indirectly.
Buried faces of box culvert, headwalls & wingwalls more than 1m below carriageway level	XC2	XD2	XF2	 Concrete buried in non-aggressive soil. Concrete surfaces exposed to de-icing salts directly/indirectly.
Exposed faces of the box culvert, headwalls & wingwalls	XC3/4	XD3	XF4	 Concrete surfaces exposed to alternate wetting and drying. Concrete surfaces within 10m of the carriageway. Concrete surfaces subjected to frequent splashing with water containing de-icing agents and exposed to freezing.

Note: The specified cover to all buried concrete within the ground shall satisfy the ground condition classification to be confirmed upon completion of the GDR (refer to section 6).

3.10.3 CONCRETE FINISHES

TABLE	TABLE 3: Concrete Finishes	
F1	All formed buried faces of box culvert, headwalls & wingwalls	
F2	All formed exposed faces of box culvert All formed faces of the headwalls & wingwalls to receive stone cladding	
F4	All formed exposed faces of the headwalls & wingwalls	
U1	All unformed buried faces of box culvert, headwalls & wingwalls	
U4	Faces of the box culvert to receive a permitted waterproofing system.	

3.10.4 DRAINAGE OF STRUCTURE

Weepholes are to be provided to the wingwalls, with a filter medium placed directly behind them to prevent backfill material loss. This shall assist in relieving the build-up of pore water pressures.

3.11. RISKS AND HAZARDS CONSIDERED FOR DESIGN, EXECUTION, MAINTENANCE AND DEMOLITION. CONSULTATIONS WITH AND/OR AGREEMENT FROM CDM CO-ORDINATOR

The Principal Designer will review the hazards and associated risks documented within the Designer's Risk Assessment contained within the pre-construction H&S file and documented on the relevant drawings as per CDM 2015.

Refer to the Designer's Risk Assessment in Appendix E for details of risks considered to date.

3.12. ESTIMATED COST OF PROPOSED STRUCTURE TOGETHER WITH OTHER STRUCTURAL FORMS CONSIDERED (INCLUDING WHERE APPROPRIATE PROPRIETARY MANUFACTURED STRUCTURE), AND THE REASONS FOR THEIR REJECTION (INCLUDING COMPARATIVE WHOLE LIFE COSTS WITH DATES OF ESTIMATES)

Details of the various structural forms considered are discussed in A59 Kex Gill Diversion – Culverts Feasibility Report dated September 2019. Refer to Appendix F.

A precast concrete box culvert was the preferred structural option as it was the most cost effective when considering capital as well as whole life cost. It also had the quickest construction time as all elements would be prefabricated and delivered/installed on site. This would significantly reduce duration for the diversion of the existing Hall Beck watercourse.

3.13. PROPOSED ARRANGEMENTS FOR CONSTRUCTION

3.13.1 CONSTRUCTION OF STRUCTURE

The final construction sequence shall be confirmed by the Principal Contractor. The design and installation of all temporary works to facilitate construction of the culvert will be the responsibility of the Principal contractor. The following construction sequence is assumed:

- 1. Set up site compound
- 2. Install Hall Beck watercourse diversion temporary works
- 3. Install temporary works to support excavation
- 4. Excavate to formation level of box culvert and wingwalls
- 5. Install precast concrete box culvert segments
- 6. Install wingwalls to both ends of the structure
- 7. Return watercourse to permanent channel
- 8. Backfill structure in a staged manner
- 9. Construct approach embankments and new A59 carriageway/bridleway provision
- 10. Install stone walls to the ends of the new culvert
- 11. Install VRS to the new A59 verges
- 12. Commission new A59 road alignment

3.13.2 TRAFFIC MANAGEMENT

Temporary traffic management for construction of the A59 Kex Gill Culvert (STR005) shall be assessed by the Principal Contractor prior to commencement of the works.

Majority of the proposed culvert is located offline from the existing A59 and therefore, it is anticipated traffic shall be maintained on the existing route as much as reasonably practical during the works.

3.13.3 SERVICE DIVERSIONS

There are no services located within the vicinity of the proposed A59 Kex Gill Culvert (STR005). However, it will be the responsibility of the Principal Contractor to identify the location of all existing statutory undertaker's services which could be affected. A comprehensive utility search will be carried out and confirmed prior to construction.

3.13.4 INTERFACE WITH EXISTING STRUCTURES

Not applicable.

4. DESIGN CRITERIA

4.1. ACTIONS

4.1.1 PERMANENT ACTIONS

Materials densities and load factors shall be in accordance with BS EN 1990 and BS EN 1991-1-1. Selected values of material densities are shown below:

TABLE 4: Material Densities (KN/m³)	
Unhardened Normal Weight Reinforced Concrete	26
Hardened Normal Weight Reinforced Concrete	25
Road Surfacing (hot rolled asphalt)	23
Normal Fill	18
6N/P Backfill	20
Steel	77
Fly Ash (PFA)	14

4.1.2 SNOW, WIND AND THERMAL ACTIONS

Snow actions - NA to BS EN 1990:2002+A1:2005 clause NA 2.3.3.3 – snow loads may generally be ignored in the UK, see NA to BS EN 1991-1-3.

Wind actions – If appropriate wind actions shall be applied in accordance with BS EN 1991-1-4:2005. Combination of wind and thermal actions - NA to BS EN 1990:2002+A1 2005 NA 2.3.3.4 - (The combination of wind and thermal actions may generally be ignored).

Thermal actions - Thermal action shall be applied in accordance with BS EN 1991-1-5:2003. Early thermal cracking will be controlled in accordance with CIRIA Document C766: Control of cracking caused by restrained deformation in concrete.

4.1.3 ACTIONS RELATING TO NORMAL TRAFFIC UNDER AW REGULATIONS AND C & U REGULATIONS

Load models LM1 – LM4 in accordance with BS EN 1991-2 modified by the UK National Annex.

4.1.4 ACTIONS RELATING TO GENERAL ORDER TRAFFIC UNDER STGO REGULATIONS

Load model LM3 in the form of SV80 & SV100 (Principal Roads) in accordance with BS EN 1991-2 modified by the UK National Annex and Table A.3 of BD100/16.

4.1.5 FOOTWAY OR FOOTBRIDGE VARIABLE ACTIONS

Not applicable.

10

4.1.6 ACTIONS RELATING TO SPECIAL ORDER TRAFFIC, PROVISION FOR EXCEPTIONAL ABNORMAL INDIVISIBLE LOADS INCLUDING LOCATION OF VEHICLE TRACK ON DECK CROSS-SECTION

Not applicable.

4.1.7 ACCIDENTAL ACTIONS

Accidental actions on the structure shall be considered in accordance with clause 4.7 of BS EN 1991-2 modified by the UK National Annex.

4.1.8 ACTIONS DURING CONSTRUCTION

The structure shall be designed for the actions in various temporary conditions taking into account changes in force distribution during the construction sequence. It is not envisaged that any unusual execution actions will occur during the construction phase.

All actions during execution shall be in accordance with Table 4.1 of BS EN 1991-1-6 modified by the UK National Annex.

Backfilling will be carried out in a staged manner so that fill levels between each culvert wall shall not differ by more than 0.5m.

4.1.9 ANY SPECIAL ACTION NOT COVERED ABOVE

BD100/16, Clause A.13 states: As the whole of the UK is considered to be an area of very low seismicity, the provision of BS EN 1998 need not apply unless otherwise specified by the TAA.

4.2. HEAVY OR HIGH LOAD ROUTE REQUIREMENTS AND ARRANGEMENTS BEING MADE TO PRESERVE THE ROUTE, INCLUDING ANY PROVISION FOR FUTURE HEAVIER LOADS OR FUTURE WIDENING

Not applicable.

4.3. MINIMUM HEADROOM PROVIDED

Approximate sizing of the proposed culvert has been based on outcome of the flood/drainage model analysis. The design assumes a 100year flood return period including a 50% climate change allowance in line with guidance given in LA 113: Road Drainage and the Water Environment.

4.4. AUTHORITIES CONSULTED AND ANY SPECIAL CONDITIONS REQUIRED

TABLE 5: Consultation Record		
AUTHORITY/STAKEHOLDER	SPECIAL CONDITIONS REQUIRED	
North Yorkshire Council (NYC)	None to date.	
Statutory Undertakers	None to date.	

4.5. STANDARDS AND DOCUMENTS LISTED IN THE TECHNICAL APPROVAL SCHEDULE

Refer to Appendix A.

4.6. PROPOSED DEPARTURES RELATING TO DEPARTURES FROM STANDARDS GIVEN IN 4.5

None.

4.7. PROPOSED DEPARTURES RELATING TO METHODS FOR DEALING WITH ASPECTS NOT COVERED BY STANDARDS IN 4.5

None.

5. STRUCTURAL ANALYSIS

5.1. METHODS OF ANALYSIS PROPOSED FOR SUPERSTRUCTURE, SUBSTRUCTURE AND FOUNDATIONS

The structure shall be analysed as a 2D plane frame on a unit width basis using MIDAS Civil or equivalent linear elastic software.

Early thermal cracking will be controlled in accordance with CIRIA Document C766: Control of cracking caused by restrained deformation in concrete.

The independent wingwalls shall be analysed as free cantilevers and designed using hand calculation. All bridge elements and temporary works including concrete and steel will be designed to limit state philosophy at both ULS and SLS in accordance with Eurocodes using linear elastic methods.

The soil has inherent stiffness and will resist deformation as defined by its modulus of subgrade reaction. Therefore, springs can be applied to the structural model to represent the subgrade reaction in the vertical direction.

Ground investigation, testing and soil capacity, will be designed to limit state philosophy in accordance with Eurocodes.

5.2. DESCRIPTION AND DIAGRAM OF IDEALISED STRUCTURE TO BE USED FOR ANALYSIS

The analysis of the structure will be carried out using a 2-dimensional plane frame model using appropriate analysis software.

Refer to Appendix D for the Idealised diagram of the structure.

5.3. ASSUMPTIONS INTENDED FOR CALCULATION OF STRUCTURAL ELEMENT STIFFNESS

For the ultimate limit state analysis, gross uncracked sections properties shall be used for all concrete elements of the structure.

5.4. PROPOSED RANGE OF SOIL PARAMETERS TO BE USED IN THE DESIGN OF EARTH RETAINING ELEMENTS

Lateral earth pressures acting on the structure shall be in accordance with document PD6694-1:2011: Recommendation for the design of structures subject to traffic loading to BS EN 1997-1:2004, using directly determined values of earth pressure coefficients present in Annex B of the document for Class 6N backfill.

6. GEOTECHNICAL CONDITIONS

6.1. ACCEPTANCE OF RECOMMENDATIONS OF THE GEOTECHNICAL DESIGN REPORT TO BE USED IN THE DESIGN AND REASONS FOR ANY PROPOSED CHANGES

A combined Ground Investigation and Geotechnical Design Report was prepared in March 2020 ("A59 Kex Gill Diversion Geotechnical Report" Ref. 70049554-001) which summarises the findings of 3No. phases of ground investigation and the geotechnical design undertaken to date.

Additional ground investigation is proposed to supplement the information above, e.g. in areas where access was constrained by soft ground/dense woodland and where structure alignments have since altered. This is due to be completed in May 2023.

6.2. SUMMARY OF DESIGN FOR HIGHWAY STRUCTURE IN THE GEOTECHNICAL DESIGN REPORT

Draft information is currently available from the additional ground investigation relating to this structure and has been used to inform the underlying ground conditions. This shall be reviewed once the final factual data has been received.

The ground conditions are anticipated to comprise:

Colluvium – Very soft slightly sandy slightly gravelly silty clay, up to ~1.5m bgl.

Highly weathered residual bedrock – Soft to firm sandy slightly gravelly clay, gravel components are of mudstone. Strata thickness between 1.0m and 2.5m.

Sandstone – Very weak to strong laminated to thickly bedded with discontinuities and occasional joints.

Mudstone - Extremely weak to weak laminated to thinly bedded highly fractured.

The Geotechnical Report recommends the culvert be founded on spread footings. The structure is assumed to found within the weathered bedrock, with a design bearing resistance for the box structure anticipated to be approximately 100kPa (Design Approach 1, Combination 2). This value is based on the assumption that horizontal loading is no greater than 50% of the vertical force. Increased bearing resistance values may be possible if the structure is founded on bedrock or if softer material encountered at formation level is excavated and replaced with granular fill material. A bearing resistance assessment should be undertaken once the loadings for the box structure and wing walls are known and supplementary ground investigation information is fully available.

6.3. DIFFERENTIAL SETTLEMENT TO BE ALLOWED FOR IN THE DESIGN OF THE STRUCTURE

The precast concrete box structure (and corresponding wingwalls) are expected to be founded either on or within close proximity to competent bedrock (1.0-2.0m). Therefore, anticipated total and differential settlement of the culvert is expected to be minimal and should be limited to 50mm and 25mm respectively.

6.4. IF THE GEOTECHNICAL DESIGN REPORT IS NOT YET AVAILABLE, STATE WHEN THE RESULTS ARE EXPECTED AND LIST THE SOURCES OF INFORMATION USED TO JUSTIFY THE PRELIMINARY CHOICE OF FOUNDATIONS

Based on the information available as reported within the Geotechnical Report, the precast concrete box culvert is anticipated to be founded on a shallow foundation. This shall be reviewed once details of the supplementary ground investigation become available, expected May 2023.

7. CHECK

7.1. PROPOSED CATEGORY AND DESIGN SUPERVISION LEVEL

The whole structure is classed as Category 1.

This indicates design supervision level DSL2 (Normal Supervision – checking by different persons than those originally responsible and in accordance with the procedure of the organisation) in accordance with Table A.2 of BD100/16.

7.2. IF CATEGORY 3, NAME OF PROPOSED INDEPENDENT CHECKER

Not Applicable.

7.3. ERECTION PROPOSALS OR TEMPORARY WORKS FOR WHICH TYPES S AND P PROPOSALS WILL BE REQUIRED, LISTING STRUCTURAL PARTS OF THE PERMANENT STRUCTURE AFFECTED WITH REASONS

All associated temporary works are to be Type S in accordance with cl. 4.2 of BD2/12.

Temporary access and platforms may be required to allow for the use of heavy plant and machinery (cranes & excavators). Local roads, culverts and bridge network will need to be capable of taking loads from vehicles associated with construction activities otherwise strengthening works may be required.

Preliminary list of temporary works to construct the A59 Kex Gill Culvert (STR005) include:

- Installation of temporary crane platforms and ramps.
- Installation of temporary works to support existing ground during excavation works.

The Principal Designer shall be responsible for the coordination of safety critical design information, this includes temporary works.

8. DRAWINGS AND DOCUMENTS

8.1. LIST OF DRAWINGS (INCLUDING NUMBERS) AND DOCUMENTS ACCOMPANYING THE SUBMISSION

- Appendix A: List of Relevant Documents from the TAS
- Appendix B: Location Plan
- Appendix C: Proposed General Arrangement Drawings
- Appendix D: Idealised Diagram
- Appendix E: Designers Risk Assessment
- Appendix F: Structure Option Feasibility
- Appendix G: TAA Correspondence

9. THE ABOVE IS SUBMITTED FOR ACCEPTANCE

Signed	
Name	
Position held	
Engineering Qualifications	
Name of Organisation	
Date	

10. THE ABOVE IS REJECTED/AGREED SUBJECT TO THE AMENDMENTS AND CONDITIONS SHOWN BELOW

Signed	
Name	
Position held	
Engineering Qualifications	
ТАА	
Date	
Signed	
Name	
Name Position held	
Position held	

Appendix A

LIST OF RELEVANT DOCUMENTS FROM THE TAS

PUBLIC | WSP

1150

TECHNICAL APPRAISAL SCHEDULE (TAS)			
1. STRUCTURAL EUROCODES			
DOCUMENT REFERENCE	TITLE	Tick if required	
BS EN 1990:2002+A1:2005	Eurocode: Basis of structural design	~	
NA to BS EN 1990:2002+A1:2005	UK National Annex to Eurocode: Basis of structural design	~	
Eurocode 1: Actions	on Structures		
BS EN 1991-1- 1:2002	Eurocode 1: Actions on structures. General Actions. Densities, self-weight, imposed load for buildings	~	
NA to BS EN 1991- 1-1:2002	UK National Annex to Eurocode 1: Actions on structures. General Actions. Densities, self-weight, imposed load for buildings	~	
BS EN 1991-1- 3:2003+A1:2015	Eurocode 1: Actions on structures. General Actions. Snow loads		
NA+A2:18 to BS EN 1991-1- 3:2003+A1:2015	UK National Annex to Eurocode 1: Actions on structures. General Actions. Snow loads		
BS EN 1991-1- 4:2005+A1:2010	Eurocode 1: Actions on structures. General Actions. Wind actions	~	
NA to BS EN 1991- 1-4:2005+A1:2010	UK National Annex to Eurocode 1: Actions on structures. General Actions. Wind actions	~	
BS EN 1991-1- 5:2003	Eurocode 1: Actions on structures. General Actions. Thermal actions	~	
NA to BS EN 1991- 1-5:2003	UK National Annex to Eurocode 1: Actions on structures. General Actions. Thermal actions	~	
BS EN 1991-1- 6:2005	Eurocode 1: Actions on structures. General Actions. Actions during execution	~	
NA to BS EN 1991- 1-6:2005	UK National Annex to Eurocode 1: Actions on structures. General Actions. Actions during execution	~	

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BS EN 1991-1- 7:2006+A1:2014	Eurocode 1: Actions on structures. General Actions. Accidental actions	~
NA+A1 to BS EN 1991-1- 7:2006+A1:2014	UK National Annex to Eurocode 1: Actions on structures. Part 1-7. Accidental actions	~
BS EN 1991-2:2003	Eurocode 1: Actions on structures. Traffic loads on bridges	~
NA to BS EN 1991- 2:2003	UK National Annex to Eurocode 1: Actions on structures. Traffic loads on bridges	~
Eurocode 2: Design	of Concrete Structures	
BS EN 1992-1- 1:2004+A1:2014	Eurocode 2: Design of concrete structures– Part 1-1: General rules and rules for buildings	~
NA + A2:2014 to BS EN 1992-1- 1:2004+A1:2014	UK National Annex to Eurocode 2: Design of concrete structures – Part 1-1: General rules and rules for buildings	~
BS EN 1992-2:2005	Eurocode 2: Design of concrete structures – Part 2: Concrete bridges – Design and detailing rules	~
NA to BS EN 1992- 2:2005	UK National Annex to Eurocode 2: Design of concrete structure – Part 2: Concrete bridges – Design and detailing rules	~
BS EN 1992-3:2006	Eurocode 2: Design of concrete structures – Part 3: Liquid retaining and containment structures	
NA to BS EN 1992- 3:2006	UK National Annex to Eurocode 2: Design of concrete structures – Part 3: Liquid retaining and containment structures	
BS EN 1992-4:2018	Eurocode 2: Design of concrete structures – Part 4: Design of fastenings for use in concrete	
NA to BS EN 1992- 4:2018	UK National Annex to Eurocode 2: Design of concrete structures – Part 4: Design of fastenings for use in concrete	

TECHNICAL APPRAISAL SCHEDULE (TAS)		
Eurocode 3: Design of Steel Structures		
BS EN 1993-1- 1:2005+A1:2014	Eurocode 3: Design of steel structures – Part 1-1 General rules and rules for buildings	
NA + A1:2014 to BS EN 1993-1- 1:2005+A1:2014	UK National Annex to Eurocode 3: Design of steel structures – Part 1-1 General rules and rules for buildings	
BS EN 1993-1- 3:2006	Eurocode 3: Design of steel structures – Part 1-3 General rules – Supplementary rules for cold-formed members and sheeting	
NA to BS EN 1993- 1-3:2006	UK National Annex to Eurocode 3: Design of steel structures – Part 1-3 Supplementary rules for cold- formed members and sheeting	
BS EN 1993-1- 4:2006	Eurocode 3: Design of steel structures – Part 1-4 General rules – Supplementary rules for stainless steels	
NA to BS EN 1993- 1-4:2006	UK National Annex to Eurocode 3: Design of steel structures – Part 1-4 Supplementary rules for stainless steels	
BS EN 1993-1- 5:2006+A1:2017	Eurocode 3: Design of steel structures – Part 1-5 Plated structural elements	
NA to BS EN 1993- 1-5:2006	UK National Annex to Eurocode 3: Design of steel structures – Part 1-5 Plated structural elements	
BS EN 1993-1- 6:2007	Eurocode 3: Design of steel structures – Part 1-6 Strength and stability of shell structures	
BS EN 1993-1- 7:2007	Eurocode 3: Design of steel structures – Part 1-7 Plated structures subject to out of plane loading	
BS EN 1993-1- 8:2005	Eurocode 3: Design of steel structures – Part 1-8 Design of joints	
NA to BS EN 1993- 1-8:2005	UK National Annex to Eurocode 3: Design of steel structures – Part 1-8 Design of joints	
BS EN 1993-1- 9:2005	Eurocode 3: Design of steel structures – Part 1-9 Fatigue	

TECHNICAL APPRAISAL SCHEDULE (TAS)			
NA to BS EN 1993- 1-9:2005	UK National Annex to Eurocode 3: Design of steel structures – Part 1-9 Fatigue		
BS EN 1993-1- 10:2005	Eurocode 3: Design of steel structures – Part 1-10 Material toughness and through-thickness properties		
NA to BS EN 1993- 1-10:2005	UK National Annex to Eurocode 3: Design of steel structures – Part 1-10 Material toughness and through thickness properties		
BS EN 1993-1- 11:2006	Eurocode 3: Design of steel structures – Part 1-11 Design of structures with tension components		
NA to BS EN 1993- 1-11:2006	UK National Annex to Eurocode 3: Design of steel structures – Part 1-11 Design of structures with tension components		
NA to BS EN 1993- 1-12:2007	UK National Annex to Eurocode 3: Design of steel structures – Part 1-12 Additional rules for the extension of EN 1993 up to steel grades S 700		
BS EN 1993-2:2006	Eurocode 3: Design of steel structures – Part 2 Steel bridges		
NA+A1:2012 to BS EN 1993-2:2006	UK National Annex to Eurocode 3: Design of steel structures – Part 2 Steel bridges		
BS EN 1993-5:2007	Eurocode 3: Design of steel structures – Part 5 Piling		
NA+A1:2012 to BS EN 1993-5:2007	UK National Annex to Eurocode 3: Design of steel structures – Part 5 Piling		
Eurocode 4: Design of Composite Steel and Concrete Structures			
BS EN 1994-1- 1:2004	Eurocode 4: Design of composite steel and concrete structures – Part 1-1 General rules and rules for buildings		
NA to BS EN 1994- 1-1:2004	UK National Annex to Eurocode 4: Design of composite steel and concrete structures – Part 1-1 General rules and rules for buildings		
BS EN 1994-2:2005	Eurocode 4: Design of composite steel and concrete structures – Part 2 General rules and rules for bridges		

TECHNICAL APPRAISAL SCHEDULE (TAS)			
NA to BS EN 1994- 2:2005	UK National Annex to Eurocode 4: Design of composite steel and concrete structures – Part 2 General rules and rules for bridges		
Eurocode 5: Design of Timber Structures			
BS EN 1995-1- 1:2004+A2:2014	Eurocode 5: Design of timber structures – Part 1-1 General – common rules and rules for buildings		
NA to BS EN 1995- 1-1:2004+A1:2008	UK National Annex to Eurocode 5: Design of timber structures – Part 1-1 General – common rules and rules for buildings		
BS EN 1995-2:2004	Eurocode 5: Design of timber structures – Part 2 Bridges		
NA to BS EN 1995- 2:2004	UK National Annex to Eurocode 5: Design of timber structures – Part 2 Bridges		
Eurocode 6: Design	of Masonry Structures		
BS EN 1996-1- 1:2005+A1:2012	Eurocode 6: Design of masonry structures – Part 1-1 General rules for reinforced and unreinforced masonry structures	~	
NA to BS EN 1996- 1-1:2005+A1:2012	UK National Annex to Eurocode 6: Design of masonry structures – Part 1-1 General rules for reinforced and unreinforced masonry structures	~	
BS EN 1996-2:2006	Eurocode 6: Design of masonry structures – Part 2 Design considerations, selection of materials and execution of masonry	~	
NA to BS EN 1996- 2:2006	UK National Annex to Eurocode 6: Design of masonry structures – Part 2 Design considerations, selection of materials and execution of masonry	~	
BS EN 1996-3:2006	Eurocode 6: Design of masonry structures – Part 3 Simplified calculation methods for unreinforced masonry structures		
NA+A1:2014 to BS EN 1996-3:2006	UK National Annex to Eurocode 6: Design of masonry structures – Part 3 Simplified calculation methods for unreinforced masonry structures		

TECHNICAL APPRAISAL SCHEDULE (TAS)		
Eurocode 7: Geotech	nnical Design	
BS EN 1997- 1:2004+A1:2013	Eurocode 7: Geotechnical design – Part 1 General rules	✓
NA+A1 to BS EN 1997- 1:2004+A1:2013	UK National Annex to Eurocode 7: Geotechnical design – Part 1 General rules	✓
BS EN 1997-2:2007	Eurocode 7: Geotechnical design – Part 2 Ground investigation and testing	\checkmark
NA to BS EN 1997- 2:2007	UK National Annex to Eurocode 7: Geotechnical design – Part 2 Ground investigation and testing	\checkmark
Eurocode 8: Design	of Structures for Earthquake Resistance	
BS EN 1998- 1:2004+A1:2013	Eurocode 8: Design of structures for earthquake resistance – Part 1 General rules, seismic actions and rules for buildings	
NA to BS EN 1998- 1:2004	UK National Annex to Eurocode 8: Design of structures for earthquake resistance – Part 1 General rules, seismic actions and rules for buildings	
BS EN 1998- 2:2005+A2:2011	Eurocode 8: Design of structures for earthquake resistance – Part 2 Bridges	
NA to BS EN 1998- 2:2005	UK National Annex to Eurocode 8: Design of structures for earthquake resistance – Part 2 Bridges	
BS EN 1998-5:2004	Eurocode 8: Design of structures for earthquake resistance – Part 5 Foundations, retaining structures and geotechnical aspects	
NA to BS EN 1998- 5:2004	UK National Annex to Eurocode 8: Design of structures for earthquake resistance – Part 5 Foundations, retaining structures and geotechnical aspects	
Eurocode 9: Design of Aluminium Structures		
BS EN 1999-1- 1:2007+A2:2013	Eurocode 9: Design of aluminium structures– Part 1-1 General structural rules	

TECHNICAL APPRAISAL SCHEDULE (TAS)

NA to BS EN 1999- 1-1:2007+A1:2009	UK National Annex to Eurocode 9: Design of aluminium structures – Part 1-1 General structural rules	
BS EN 1999-1- 3:2007+A1:2011	Eurocode 9: Design of aluminium structures – Part 1-3 Structures susceptible to fatigue	
NA to BS EN 1999- 1-3:2007+A1:2011	UK National Annex to Eurocode 9: Design of aluminium structures – Part 1-3 Structures susceptible to fatigue	
BS EN 1999-1- 4:2007+A1:2011	Eurocode 9: Design of aluminium structures – Part 1-4 Cold formed structural sheeting	
NA to BS EN 1999- 1-4:2007	UK National Annex to Eurocode 9: Design of aluminium structures – Part 1-4 Cold formed structural sheeting	

2. BSI PUBLISHED DOCUMENTS

DOCUMENT REFERENCE	TITLE	Tick if required
PD 6688-1-1:2011	Recommendations for the design of structures to BS EN 1991-1-1	~
PD 6688-1-4:2015	Background paper to the UK National Annex to BS EN 1991-1-4	~
PD 6688-1- 7:2009+A1:2014	Recommendations for the design of structures to BS EN 1991-1-7	~
PD 6688-2:2011	Recommendations for the design of structures to BS EN 1991-2	~
PD 6687-1:2010	Background paper to the UK National Annexes to BS EN 1992-1 and BS EN 1992-3	~
PD 6687-2:2008	Recommendations for the design of structures to BS EN 1992-2:2005	~
PD 6694-1:2011	Recommendations for the design of structures subject to traffic loading to BS EN 1997-1	~
PD 6678:2005	Guide to the specification of masonry mortar	\checkmark

TECHNICAL APPRA	ISAL SCHEDULE (TAS)	
PD 6695-1-9:2008	Recommendations for the design of structures to BS EN 1993-1-9	
PD 6695-1-10:2009	Recommendations for the design of structures to BS EN 1993-1-10	
PD 6695-2:2008 + A1:2012 Incorporating Corrigendum No.1	Recommendation for the design of bridges to BS EN 1993	
PD 6696- 2:2007+A1:2012	Background paper to BS EN 1994-2 and the UK National Annex to BS EN 1994-2	
PD 6698:2009	Recommendations for the design of structures for earthquake resistance to BS EN 1998	
PD 6702-1:2009	Structural use of aluminium. Recommendations for the design of aluminium structures to BS EN 1999	
PD 6703:2009	Structural bearings – Guidance on the use of structural bearings	
PD 6705- 2:2010+A1:2013	Recommendations for the execution of steel bridges to BS EN 1090-2	
PD 6705-3:2009	Recommendations on the execution of aluminium structures to BS EN 1090-3	
PD CEN-TR 1295- 2:2005	Structural design of buried pipelines under various conditions of loading	
	Part 2: Summary of nationally established methods of design	
3. EXECUTION S	STANDARDS	
DOCUMENT REFERENCE	TITLE	Tick if required
BS EN 1090- 1:2009+A1:2011	Execution of steel structures and aluminium structures. Requirements for conformity assessment of structural components	

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BS EN 1090-2:2018	Execution of steel structures and aluminium structures. Technical requirements for the execution of steel structures	
BS EN 1090-3:2008	Execution of steel structures and aluminium structures. Technical requirements for the execution of aluminium structures	
BS EN 1536:2010+A1:2015	Execution of Special geotechnical works. Bored Piles	
BS EN 12063:1999	Execution of special geotechnical work. Sheet pile walls	
BS EN 13670:2009 Incorporating corrigenda October 2015 and November 2015	Execution of concrete structures	~
4. PRODUCT ST	ANDARDS	
DOCUMENT REFERENCE	TITLE	Tick if required
BS EN 206:2013+A1:2016	Concrete. Specification, performance, production and conformity	~
BS EN 10080:2005	Steel for the reinforcement of concrete — Weldable reinforcing steel - General	
BS EN 13369:2013	Common rules for precast concrete products	✓
BS EN 15050:2007+A1:201 2	Precast concrete products. Bridge elements	~
BS EN 14844:2006 (+A2:2011)	Precast concrete products - Box culverts	✓
BS EN 1317-1:2010	Road restraint systems – Part 1 Terminology and general criteria for test methods	✓

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BS EN 1317-2:2010	Road restraint systems – Part 2 Performance classes, impact test acceptance criteria and test methods for safety barriers	√
BS EN 998-2:2016	Specification for mortar for masonry – Part 2: Masonry mortar	\checkmark
BS EN 1317-3:2010	Road restraint systems – Part 3 Performance classes, impact test acceptance criteria and test methods for crash cushions	
DD ENV 1317- 4:2002	Road restraint systems – Part 4 Performance classes, impact test acceptance criteria and test methods for terminals and transitions of safety barriers	
BS EN 1317- 5:2007+A2:2012	Road restraint systems – Part 5 Product requirements and evaluation of conformity for vehicle restraint systems	
PD CEN/TR 16949:2016	Road restraint systems – Part 6 Pedestrian restraint systems. Pedestrian Parapets	
Draft prEN 1317-7	Road restraint systems – Part 7 Performance classes, impact test acceptance criteria and test methods for terminals of safety barriers	
PD CEN/TR 17081:2018	Design of fastenings for use in concrete – Plastic design of fastenings with headed and post-installed fasteners	
BE EN 1317-8:2012	Road restraint systems – Part 8 Motorcycle road restraint systems which reduce the impact severity of motorcyclist collisions with safety barriers	
BS EN 1337-1:2000	Structural Bearings – Part 1 General Design Rules	
BS EN 1337-2:2004	Structural Bearings – Part 2 Sliding Elements	
BS EN 1337-3:2005	Structural Bearings – Part 3 Elastomeric Bearings	
BS EN 1337-4:2004	Structural Bearings – Part 4 Roller Bearings	
BS EN 1337-5:2005	Structural Bearings – Part 5 Pot Bearings	
BS EN 1337-6:2004	Structural Bearings – Part 6 Rocker Bearings	

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BS EN 1337-7:2004	Structural Bearings – Part 7 Spherical and cylindrical PTFE bearings	
BS EN 1337-8:2007	Structural Bearings – Part 8 Guide bearings and Restraint bearings	
BS EN 1337-9:1998	Structural Bearings – Part 9 Protection	
BS EN 1337-10:2003	Structural Bearings – Part 10 Inspection and Maintenance	
BS EN 1337-11:1998	Structural Bearings – Part 11 Transport, storage and installation	
BS EN 1794-1:2018	Road traffic noise reducing devices. Non-acoustic performance. Mechanical performance and stability requirements	
BS EN 1794-2:2011	Road traffic noise reducing devices. Non-acoustic performance. General safety and environmental requirements	
BS EN 10025-1:2004	Hot rolled products of structural steels – Part 1 General technical delivery conditions	
BS EN 10025-2:2004	Hot rolled products of structural steels – Part 2 Technical delivery conditions for non-alloy structural steels	
BS EN 10025-3:2004	Hot rolled products of structural steels – Part 3 Technical delivery conditions for normalized/normalized rolled weldable fine grain structural steels	
BS EN 10025-4:2004	Hot rolled products of structural steels – Part 4 Technical delivery conditions for thermomechanical rolled weldable fine grain structural steels	
BS EN 10025-5:2004	Hot rolled products of structural steels – Part 5 Technical delivery conditions for structural steels with improved atmospheric corrosion resistance	
BS EN 10025- 6:2004+A1:2009	Hot rolled products of structural steels – Part 6 Technical delivery conditions for flat products of high yield strength structural steels in the quenched and tempered condition	

TECHNICAL APPRAI	SAL SCHEDULE (TAS)	
BS EN 10080:2005	Steel for the reinforcement of concrete. Weldable reinforcing steel. General	
BS EN 10210-1:2006	Hot finished structural hollow sections of non-alloy and fine grain steels – Part 1 Technical delivery requirements	
BS EN 10210-2:2006	Hot finished structural hollow sections of non-alloy and fine grain steels – Part 2 Tolerances, dimensions and sectional properties	
BS EN 10248-1:1996	Hot rolled sheet piling of non-alloy steels – Part 1 Technical delivery conditions	
BS EN 10248-2:1996	Hot rolled sheet piling of non-alloy steels – Part 2 Tolerances on shape and dimensions	
BS EN 14388:2005	Road traffic noise reducing devices	
BS EN 1295-1:1997	Structural design of buried pipelines under various conditions of loading	
	Part 1: General requirements	
BS EN 1916:2002	Concrete pipes and fittings, unreinforced, steel fibre and reinforced	
5. BRITISH STAN	IDARDS	
DOCUMENT REFERENCE	TITLE	Tick if required
BS 4449:2005 +A3:2016	Steel for the reinforcement of concrete	~
BS 5896:2012	Specification of high tensile steel wire and strand for the prestressing of concrete	
BS 7818:1995	Specification for pedestrian restraint systems in metal	
BS 8002:2015	Code of practice for earth retaining structures	~
BS 8004:2015	Code of practice for foundations	✓

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BS 8006- 1:2010+A1:2016	Code of practice for strengthened/reinforced soils and other fills	
BS 8500- 1:2015+A2:2019	Concrete – Complementary British Standard to BS EN 206 Part 1 – Method of specifying and guidance for the specifier	~
BS 8500- 2:2015+A2:2019	Concrete – Complementary British Standard to BS EN 206 Part 2 – Specification for constituent materials and concrete	~
BS 8666:2005	Scheduling, dimensioning, bending and cutting of steel reinforcement for concrete	~
BS 5628-1:1992	Code of practice for use of masonry Part 1: Structural use of unreinforced masonry	~
BS 5911-1:2002	Concrete pipes and ancillary concrete products Part 1: Specification for unreinforced and reinforced concrete pipes (including jacking pipes) and fittings with flexible joints	
BS 9295:2010	Guide to the structural design of buried pipelines	
6. DESIGN MAN	JAL FOR ROADS AND BRIDGES (DMRB)	I
6.1 ADVICE NOTE	S – BRIDGES AND STRUCTURES (BA SERIES)	
DOCUMENT REFERENCE	TITLE	Tick if required
BA 9/81	The Use of BS 5400 Part 10: 1980 - Code of Practice for Fatigue [Incorporating Amendment No.1 dated November 1983	
BA 19/85	The Use of BS 5400: Part 3: 1982	
CD 357	Bridge Expansion Joints	~

TECHNICAL APPRAISAL SCHEDULE (TAS)		
CD 355	Application of whole-life costs for design and maintenance of highway structures	\checkmark
BA 35/90	Inspection and Repair of Concrete Highway Structures Not applicable for use in Scotland Northern Ireland Addendum applicable for use in Northern Ireland	
BA 36/90	The Use of Permanent Formwork	
BA 37/92	Priority Ranking of Existing Parapets	
BA 38/93	Assessment of the Fatigue Life of Corroded or Damaged Reinforcing Bars	
BA 39/93	Assessment of Reinforced Concrete Half-joints	
BA 40/93	Tack Welding of Reinforcing Bars	
BA 41/98	The Design and Appearance of Bridges	\checkmark
BA 51/95	The Assessment of Concrete Structures Affected by Steel Corrosion	
BA 52/94	The Assessment of Concrete Structures Affected by Alkali Silica Reaction	
CS 463	Load Testing for Bridge Assessment	
CS 459	The Assessment of bridge substructures, retaining structures and buried structures	
BA 57/01	Design for Durability	\checkmark
CD 356	Design of highway structures for hydraulic actions	\checkmark
CD 362	Enclosure of Bridges	
BA 68/97	Crib Retaining Walls	
BA 72/03	Maintenance of Road Tunnels	
BA 74/06	Assessment of Scour at Highway Bridges	\checkmark

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BA 82/00	Formation of Continuity Joints in Bridge Decks	
CD 370	Cathodic Protection for Use in Reinforced Concrete Highway Structures	
BA 85/04	Coatings for Highway Structures and Ancillary Structures	~
CS 464	Non-Destructive Testing of Highway Structures	
CS 460	Management of Corrugated Steel Buried Structures	
BA 88/04	Management of Buried Concrete Box Structures	~
BA 92/07	The Use of Recycled Concrete Aggregates in Structural Concrete	~
BA 93/09	Structural Assessment of Bridges with Deck Hinges	
6.2 STANDARDS	- BRIDGES AND STRUCTURES (BD SERIES)	I
DOCUMENT REFERENCE	TITLE	Tick if required
BD 2/12	Technical Approval of Highway Structures	~
BD 9/81	Implementation of BS 5400: Part 10: 1980 - Code of Practice for Fatigue	
CD 361	Weathering Steel for Highway Structures	
BD 13/06	Design of Steel Bridges. Use of BS 5400-3:2000	
CD 365	Portal and cantilever signs/signals gantries	
CD 375	Design of corrugated steel buried structures	
CS 454	Assessment of Highway Bridges and Structures	
BD 29/17	Design Criteria for Footbridges	
BD 31/01	The Design of Buried Concrete Box and Portal Frame Structures	~

TECHNICAL APPRAISAL SCHEDULE (TAS)		
BD 33/94	Expansion Joints for Use in Highway Bridge Decks	~
CG 303	Quality Assurance Scheme for Paints and Similar Protective Coatings	
BD 36/92	Evaluation of Maintenance Costs in Comparing Alternative Designs for Highway Structures	~
BD 41/97	Reinforced Clay Brickwork Retaining Walls of Pocket Type and Grouted Cavity Type Construction	
BD 43/03	The Impregnation of Reinforced and Prestressed Concrete Highway Structures using Hydrophobic Pore- Lining Impregnants	~
BD 44/15	The Assessment of Concrete Highway Bridges and Structures	
BD 45/93	Identification Marking of Highway Structures	~
CD 358	Waterproofing and Surfacing of Concrete Bridge Decks	~
BD 48/93	The Assessment and Strengthening of Highway Bridge Supports	
BD 49/01	Design Rules for Aerodynamic Effects on Bridges	
BD 54/15	Management of Post-Tensioned Concrete Bridges	
BD 53/95	Inspection & Records for Road Tunnels	
BD 56/10	The Assessment of Steel Highway Bridges and Structures	
BD 57/01	Design for Durability	~
BD 60/04	Design of Highway Bridges for Vehicle Collision Loads	
BD 61/10	The Assessment of Composite Highway Bridges and Structures	
BD 62/07	As Built, Operational and Maintenance Records for Highway Structures	~

TECHNICAL APP	PRAISAL SCHEDULE (TAS)	
BD 63/17	Inspection of Highway Structures	\checkmark
BD 65/14	Design Criteria for Collision Protector Beams	
BD 78/99	Design of Road Tunnels	
BD 79/13	The Management of Sub-standard Highway Structures	
CD 360	Use of Compressive Membrane Action in Bridge Decks	
BD 82/00	Design of Buried Rigid Structures	
BD 84/02	Strengthening of Concrete Bridge Supports for Vehicle Impact Using Fibre Reinforced Polymers	
BD 85/08	Strengthening Highway Structures Using Externally Bonded Fibre Reinforced Polymer	
BD 86/11	The Assessment of Highway Bridges and Structures For The Effects of Special Types General Order (STGO) and Special Order (SO) Vehicles	
BD 87/05	Maintenance Painting of Steelwork	
BD 89/03	The Conservation of Highway Structures English Addendum applicable for use in England Northern Ireland Addendum applicable for use in Northern Ireland Scottish Addendum applicable for use in Scotland Welsh Addendum applicable for use in Wales	
BD 90/05	Design of FRP Bridges and Highway Structures	
BD 91/04	Unreinforced Masonry Arch Bridges	
BD 94/17	Design of Minor Structures	\checkmark
BD 95/07	Treatment of Existing Structures on Highway Widening Schemes	
BD 97/12	The Assessment of Scour and Other Hydraulic Actions at Highway Structures	\checkmark
BD 100/16	The Use of Eurocodes for the Design of Highway Structures	✓

TECHNICAL APPRAI	SAL SCHEDULE (TAS)	
BD 101/11	Structural Review and Assessment of Highway Structures	
6.3 TECHNICAL N	IEMORANDA – BRIDGES (BE SERIES)	
DOCUMENT REFERENCE	TITLE	Tick if required
BE 5/75	Technical Memorandum (Bridges)	
	Rules for the Design and Use of Freyssinet Concrete Hinges in Highway Structures	
6.4. STANDARDS	- GENERAL REQUIREMENTS (GD SERIES)	
GG 101	Introduction to the Design Manual for Roads and Bridges	~
GG 102	Quality Management Systems for Highway Works	
GG 104	Requirements for Safety Risk Assessment	~
GD 02/16	Quality Management Systems for Highway Design	
GD 5/16	Asbestos Management in Trunk Road Assets	
GD 300	Requirements for new and upgraded all-purpose trunk roads (expressways)	
6.5 ADVICE NOTE	S - HIGHWAYS (HA SERIES)	
DOCUMENT REFERENCE	TITLE	Tick if required
HA 40/01	Determination of Pipe Bedding Combinations for Drainage Works	
HA 59/92	Mitigating against Effects on Badgers (Incorporating Amendment No. 1 dated February 1997)	~
HA 65/94	Design for Environmental Barriers	
HA 66/95	Environmental Barriers – Technical Requirements	

TECHNICAL APP	PRAISAL SCHEDULE (TAS)	
HA 74/07	Treatment of Fill and Capping Materials Using Either Lime or Cement or Both	
HA 75/01	Trunk Roads and Archaeological Mitigation	
CD 521	Hydraulic design of road edge surface water channels and outlets	
HA 80/99	Nature Conservation Advice in Relation to Bats	✓
HA 81/99	Nature Conservation Advice in Relation to Otters	\checkmark
HA 84/01	Nature Conservation and Biodiversity	\checkmark
HA 97/01	Nature Conservation Management Advice in Relation to Dormice	~
HA 98/01	Nature Conservation Management Advice in Relation to Amphibians	✓
HA 106/04	Drainage of Runoff from Natural Catchments	\checkmark
HA 107/04	Design of Outfall and Culvert Details	\checkmark
HA 116/05	Nature Conservation Advice in Relation to Reptiles and Roads	
HA 117/08	Cultural Heritage Asset Management Plans	
HA 200/08	Aims and Objectives of Environmental Assessment	
HA 201/08	General Principles and Guidance of Environmental Impact Assessment	✓
HA 202/08	Environmental Impact Assessment	
HA 204/08	Scoping of Environmental Impact Assessments	
HA 205/08	Assessment and Management of Environmental Effects	
HA 207/07	Air Quality	
HA 208/07	Cultural Heritage	\checkmark

TECHNICAL APP	RAISAL SCHEDULE (TAS)	
HA 212/08	Glossary of Terms Used in The Design Manual for Roads and Bridges Volume 11 Sections 1 and 2	
CD 523	Determination of pipe roughness and assessment of sediment deposition to aid pipeline design	
6.6 STANDAR	DS - HIGHWAYS (HD SERIES)	
DOCUMENT REFERENCE	TITLE	Tick if required
CD 622	Managing Geotechnical Risk	✓
HD 33/16	Design of Highway Drainage Systems	✓
HD 41/15	Maintenance of Highway Geotechnical Assets	~
HD 44/09	Assessment of Implications (of Highways and/or Roads Projects) on European Sites (Including Appropriate Assessment)	
LA 113	Road Drainage and the Water Environment	✓
HD 47/08	Screening of Projects for Environmental Impact Assessment	
HD 48/08	Reporting of Environmental Impact Assessments	
HD 49/16	Highway Drainage Design Principal Requirements	
HD 50/16	The Certification of Drainage Design	
HD 213/11	Noise and Vibration	
6.7 STANDAR	DS – TRAFFIC ENGINEERING AND CONTROL (TD SERIES))
DOCUMENT REFERENCE	TITLE	Tick if required
TD 9/93	Highway Link Design (Incorporating Amdt No 1 dated February 2002)	

TECHNICAL APPRAISAL SCHEDULE (TAS)				
TD 19/06	Requirement for Road Restraint Systems	\checkmark		
TD 27/05	Cross Sections and Headroom	\checkmark		
TD 36/93	Subways for Pedestrians and Pedal Cyclists, Layout and Dimensions			
CD 169	The design of lay-bys, maintenance hardstandings, rest areas, service areas and observation platforms			
7. MANUAL OF	CONTRACT DOCUMENTS FOR HIGHWAY WORKS (MCD	HW)		

DOCUMENT TITLE	Tick if required
Volume 1: Specification for Highway Works (May 2017)	\checkmark
Volume 2: Notes for Guidance on the Specification for Highway Works (May 2017)	~
Volume 3: Highway Construction Details (February 2017)	~

8. INTERIM ADVICE NOTES

(Which may be used with additional guidance and/or requirement as in BD 100)

IAN 69/15	Designing for Maintenance	~
IAN 83/06	Principal and General Inspection of Sign/Signal Gantries, and Gantries with low handrails or open mesh flooring	
IAN 97/07	Assessment and upgrading of existing parapets	
IAN 104/15	The Anchorage of Reinforcement & Fixings in Hardened Concrete	~
IAN 105/08	Implementation of construction (Design and Management) 2007 and the withdrawal of SD 10 and SD 11	~
IAN 117/08r2	Certification of combined kerb and drainage products	
IAN 124/11 Annex C	Use of Eurocodes for the design of highway structures	~

		T
IAN 127/10r1	The use of foamed concrete	
IAN 131/11	Deflection of Permanent Formwork	
IAN 136/10	Structural safety reporting	
IAN 149/17	Existing Motorway Minimum Requirements	
IAN 161/15	Smart Motorways	
IAN 173/13	Implementation of BD97/12 The Assessment of Scour and Other Hydraulic Actions at Highway Structures	~
IAN 184/16	Highways Agency Data & CAD Standard	~
9. HA PUBL	ICATIONS (TSE)	<u>.</u>
DOCUMENT TIT	LE	Tick if required
TRH 1679 Issue	A July 1997 Controlled Motorway – Controlled Motorway al (Structures)	
	January 1999 Message Signs and Motorway Signals MK 3 ents for Enclosures and Mounting Brackets	
	January 1999 Message Signs and Motorway Signals MK 3	
	ents for Portal Gantry Interface Frames	
(MS3) Requireme	C July 1999 Message Signs and Motorway Signals MK 3 (MS3)	
(MS3) Requireme TRH 1642 Issue Infrastructure Des	C July 1999 Message Signs and Motorway Signals MK 3 (MS3) sign Guide Drawings, Specifications and Instruction: Traffic Systems and	
(MS3) Requireme TRH 1642 Issue Infrastructure Des DETR/HA List of Lighting, MCS 20	C July 1999 Message Signs and Motorway Signals MK 3 (MS3) sign Guide Drawings, Specifications and Instruction: Traffic Systems and	
(MS3) Requireme TRH 1642 Issue Infrastructure Des DETR/HA List of Lighting, MCS 20	C July 1999 Message Signs and Motorway Signals MK 3 (MS3) sign Guide Drawings, Specifications and Instruction: Traffic Systems and 6 ANEOUS PUBLICATIONS	Tick if required


TECHNICAL APPRAISAL SCHEDULE (TAS)	
CIRIA Document C524: Cladding Fixings	\checkmark
CIRIA Document C543: Bridge Detailing Guide	~
CIRIA Document C579: Retention of Masonry Facades – best practice guide	~
CIRIA Document C641: EC7 – Implications for UK Practice	~
CIRIA Document C660: Early-age thermal crack control in concrete	~
CIRIA Document C686: Safe Access for Maintenance and Repair	~
CIRIA Document C689: Culvert Design and Operation Guide	~
CIRIA Document C760: Guidance on Embedded Retaining Wall Design	
CIRIA Document C766: Control of cracking caused by restrained deformation in concrete	✓
CIRIA Document C777: General Fixings – Guidance on Selection and whole-life Management	
CIRIA Document C778: Management of Safety-critical fixings	
Circular Roads No. 61/72 – Routes for Heavy and High Abnormal Loads	
The Traffic Signs Regulations and General Directions 1994 (S.I. 1994 No. 1519)	
Simplified Tables of External Loads on Buried Pipelines (1986) – TRRL	
Health and Safety at Work Act 1974	\checkmark
The Construction (Design and Management) Regulation 2007 (HSE)	~
Control of Substances Hazardous to Health Regulations 1994 (HSE)	


Appendix B

LOCATION PLAN


CONFIDENTIAL | WSP

wsp










base Rights 2023 Ordnance Survey 100018928	 THIS DRAY PROPOSE IMPROVEM THE DIVEN AS INCLUI COMPRISE 3NO. EXIS 2NO. EXIS 2NO. PRO 8NO. PRO 	WING PROVIDE D STRUCTURE MENT SCHEME. RSION SHALL A DE PROPOSALS NG: TING CULVERT TING BRIDGES POSED UNDER POSED UNDER POSED CULVEP POSED RETAIN	S REQUIRED FFECT 5NO. S FOR 11NO. S PASSES RTS	FOR THE A	59 KI TRU(EX GIL CTURI	
	KEY:	- EXIST	STRUCTURE	URE TO BE			
D- Blubberhuses Bridge 1877 7m 1877 7m Car Park Stone							
	_						
	P08 15/05/2023 Rev. Date	UPDATED FOR AIP R	Description		SH By	DM Chk'd	DM App'd
	Rev. Date	hite Rose Office Park T+ 44 (0) 113 39		ane, Leeds, LS1 113 395 6201	Ву	Chk'd	
	Rev. Date	hite Rose Office Park T+ 44 (0) 113 39	Description	ane, Leeds, LS1 113 395 6201	Ву	Chk'd	
	Rev. Date Rev. Date	hite Rose Office Park T+ 44 (0) 113 39 A59 KEX TRUCTURE	Description	ane, Leeds, LS1 113 395 6201 Shire Incil	By	Chk'd	
	Rev. Date Rev. Date	hite Rose Office Park T+ 44 (0) 113 39 A59 KEX TRUCTURE	Description	ane, Leeds, LS1 113 395 6201 Shire Incil	ву 1 ODL,	Chk'd	App'd
	Rev. Date Rev. Date Three W Three W Client Client Project Title S Drawing Title S Scale N/A Original Size A1	hite Rose Office Park T+ 44 (0) 113 390 Notes that the second sec	Description	Ane, Leeds, LS1 113 395 6201 Schire CION PLA 3)	Ву 1 ODL, N	UK UK uthorised H.Mis ate 31/01/2	App'd
	Rev. Date Rev. Date Three W Three W Client Three W Client Scale Drawing Title S Scale N/A Original Size A1 Drawing Status Status	hite Rose Office Park T+ 44 (0) 113 394 A59 KEX TRUCTURE (SHI Drawn L. Slinn Date	Description	Ane, Leeds, LS1 113 395 6201 Shire Concil ERSION TON PLA 3) Approved H.Mistry Date	Ву 1 ODL, N	UK UK uthorised H.Mis ate	App'd
	Rev. Date Rev. Date Three W Three W Client Three W Client Scale Drawing Title S Scale N/A Original Size A1 Drawing Status Status	hite Rose Office Park T+ 44 (0) 113 393 None Content A59 KEX TRUCTURE (SHI Drawn L. Slinn Date 31/01/2020	Description	Ane, Leeds, LS1 113 395 6201 CShire CION PLA 3) Approved H.Mistry Date 31/01/202	Ву 1 ODL, N А О С Р	UK UK UK uthorised H.Mis ate 31/01/2 Suitabilit	App'd

Appendix C


PROPOSED GENERAL ARRANGEMENT DRAWINGS


CONFIDENTIAL | WSP

NSD





Ξ






		Survey 100018928 NOTES GENERAL
		 ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE. ALL LEVELS ARE IN METRES AOD UNLESS NOTED OTHERWISE.
		 DO NOT SCALE FROM THIS DRAWING. THE DRAWING TO BE READ IN CONJUNCTION WITH THE SPECIFICATION FOR HIGHWAY WORKS, CONTRACT-SPECIFIC
	WING SCHEDULE	APPENDICES, DRAWINGS NYKGDD-WSP-SMN-ALL-DR-CB-0001, AND NYKGDD-WSP-SMN-ALL-DR-CB-0002, AND THE DRAWINGS
DRAWING NUMBER NYKGDD-WSP-SMN-	TITLE GENERAL ARRANGEMENT	LISTED IN THE SCHEDULE ON THIS DRAWING.5. THE CONTRACTOR SHALL MEASURE AND CONFIRM ALL DIMENSIONS/LEVELS THAT HAVE A DIRECT IMPACT ON THE WORKS
ST005-DR-CB-0001 NYKGDD-WSP-SMN-	SHEET 1 OF 2 GENERAL ARRANGEMENT	PRIOR TO EXECUTION. IN CASE OF DOUBTS, OMISSIONS, OR ERRORS, THE CONTRACTOR NEEDS TO SEEK CLARIFICATION FROM THE NEC4 PROJECT MANAGER.
ST005-DR-CB-0002	SHEET 2 OF 2	 FOR THE AFFECTED AREAS PRIOR TO WORKS, THE CONTRACTOR SHALL OBTAIN UP-TO-DATE UTILITY PLANS AND CARRY OUT
NYKGDD-WSP-SMN- ALL-DR-CB-0001	TYPICAL CULVERT DETAILS SHEET 1 OF 2	SURVEYS TO POSITIVELY IDENTIFY AND MARK-UP ANY UTILITY APPARATUS. REFER TO APPENDIX 1/16 FOR FURTHER INFORMATION. GEOTECHNICAL
NYKGDD-WSP-SMN- ALL-DR-CB-0002	TYPICAL CULVERT DETAILS SHEET 2 OF 2	 FORMATION INSPECTIONS SHALL BE UNDERTAKEN BY THE DESIGNER'S SITE REPRESENTATIVE WHO SHALL BE A
		SUITABLY QUALIFIED GEOTECHNICAL ENGINEER. THE STRUCTURE IS ASSUMED TO FOUND ON WEATHERED BEDROCK. ANY SOFT SPOTS SHALL BE EXCAVATED AND REPLACED IN ACCORDANCE WITH THE RELEVANT STANDARD EARTHWORKS DETAILS AND IN ACCORDANCE WITH THE SERIES 600 SPECIFICATION. THE DESIGNER SHALL BE INFORMED IMMEDIATELY IF FORMATION MATERIAL DIFFERS FROM THAT ASSUMED WITHIN THE DESIGN.
 DIVERSION TEN 3. INSTALL TEMPORSUPPORT EXC. 4. EXCAVATE TO BOX CULVERT 5. INSTALL PRECACULVERT SEGN 6. INSTALL NATUPPROGRESS TO SPACE WORKING 7. INSTALL WINGACOF THE STRUCT 8. RETURN WATE PERMANENT CONSTRUCT A EMBANKMENTS CARRIAGEWAY 11. INSTALL RAISE ENDS OF THE MANANER 	OMPOUND BECK WATERCOURSE MPORARY WORKS ORARY WORKS TO AVATION FORMATION LEVEL OF AND WINGWALLS AST CONCRETE BOX MENTS RAL BED AS CULVERT OREDUCE CONFINED NG WALLS TO BOTH ENDS CTURE RECOURSE TO HANNEL UCTURE IN A STAGED PPROACH S, NEW A59 (AND BRIDLEWAY ED STONE WALL TO THE NEW CULVERT TO THE NEW A59 VERGES	 8. PRECAST UNITS FOUNDED ON OTHER THAN HARD MATERIAL (E.G.: NOT ON BEDROCK OR PILED SLABS) SHALL BE LAID ON EITHER: A GRANULAR BED WITH THE LOWER 150MM BEING 6N MATERIAL AND THE UPPER 50MM BEING CLASS 6L MATERIAL AS PER MCHW SERIES 600, EXCEPT FOR CLASS 6L, ONLY THE GRADING REQUIREMENT APPLIES AND NOT THE OTHER MATERIAL PROPERTIES LISTED IN TABLE 6/1 OF MCHW (BUT THE SULPHATE REQUIREMENTS OF CLAUSE 601 STILL APPLY). ALTERNATIVELY, THE LOWER 150MM MAY BE REPLACED BY A 75MM MINIMUM THICKNESS BLINDING CONCRETE COMPRISING DESIGNATED CONCRETE FND2. EITHER BEDDING OPTION TO BE A MIN 300MM WIDER THAN THE PRECAST ELEMENTS AT OUTER EDGES. 9. THE LEVEL OF THE BOTTOM OF PRECAST UNITS TO BE ADJUSTED BASED ON THICKNESS OF CONTRACTOR DESIGNED PRECAST BOX BOTTOM SLAB IN ORDER TO ACHIEVE STATED INVERT LEVELS (ASSSUMED 200MM SLAB THICKNESS WITH 300MM NATURAL BED SHOWN ON THIS DRAWING). STONE FACING AND STONE WALLS 10. REFER TO DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002 AND SPECIFICATION APP 24/1 FOR DETAILS.
		INDICATES A RESIDUAL RISK AS A WARNING
		IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 006 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES
		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 006 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS
6N BACKFILL		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 006 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS
6N BACKFILL		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 005 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES Image: Im
6N BACKFILL		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 006 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES Image: Construct of the structure of t
6N BACKFILL		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 005 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES Image: Im
6N BACKFILL		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 005 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES
		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 007 - WORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES
6N BACKFILL PRECAST BOX BASE LEVEL - SEE NOTE 9		DRAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 005 - BACKFILLING OF THE BOX CULVERT STRUCTURE REF 007 - OWORKING WITH LIFTING PLANT DURING INSTALLATION OF PRECAST UNITS REF 009 - DAMAGE TO EXISTING STATUTORY SERVICES Image:
PRECAST BOX BASE LEVEL - SEE NOTE 9		DRAWING, NOTE THE FOLLOWING GUMPICANT RESIDUAL, RISKS CONSTRUCTION REF 000 - MARKING IN CONFINED SPACE REF 000 - MARKING THE INTO LAWRING INSTALLATION OF PRECAST UNITS REF 000 - DAMAGE TO EXISTING STATUTORY SERVICES Image: Construction Image: Co
PRECAST BOX BASE LEVEL - SEE NOTE 9		PRAVING, NOTE THE FOLLOWING SIGNAFICANT RESIDUAL, RISKS CONSTRUCTION REF 004 - WORKING IN CONFINED SPACE REF 004 - WORKING IN THE BOX AULTURING INSTALLATION OF PRECAST UNITS REF 004 - WORKING STATUTORY SERVICES Image: International Configuration of the Box Automation installation of PRECAST UNITS REF 004 - WORKING STATUTORY SERVICES Image: International Configuration of the Box Automation installation of PRECAST UNITS REF 004 - DAMAGE TO EXISTING STATUTORY SERVICES Image: International Configuration of the Box Automation of Box Applied P04 11/05/2023 UPDATED FOR AIP REVISION SH DM DM Rev. Date Description By Check did Applid Note: Three While Rose Office Park, Milehaw Park Lane, Leeds, LS11 ODL, UK T+ 44 (0) 113 395 6201 Wegoon Client Image: Control Control Control Section Sectio
PRECAST BOX BASE LEVEL - SEE NOTE 9		DRAWING, NOTE THE FOLLOWING SIGNAFICANT RESIDUAL, RISKS CONSTRUCTION REF 001 - BACKFLILING OF THE BOX CULVERT STRUCTURE REF 000 - DARAGE TO EXISTING STATUTORY SERVICES Image: Internet internet part of the Internet part o
PRECAST BOX BASE LEVEL - SEE NOTE 9	CTION - SCOUR PROTECTION OR SIMI (FOR DETAILS REFER TO DRA	Drawming, NOTE THE FOLLOWING BIGNELICANT RESIDUAL RESKS INFER 004 - VORTING STATUTORY SERVICES INFER 007 - VORTING TO LISTING STATUTORY SERVICES INFER 007 - VORTING VORTING WEAT LATER, LATER, LOTING AND
PRECAST BOX BASE LEVEL - SEE NOTE 9	CTION - SCOUR PROTECTION OR SIMI	Determine State Counter Structure REF 002 - VOORNOU NO CONFINED BYACE REF 002 - VOORNOU NOT TO FUNCTORE REF 002 - VOORNOU NOT TO FUNCTORE TO DETERMINE OF THE COUNT DESTRUCTURE REF 002 - VOORNOU NOT TO FUNCTORE INFORMULE TING PLANT TO FUNCTORE INFORMATION OF PRECIDENT INFORMATION INFORMATION INFORMATION






2023 Ordnance Survey 100018928	INOILS							
	GENEF 1. A		NSIONS ARE IN	MM UNLESS N	IOTED OTHE	ERWIS	E.	
	2. A	LL LEVEL	S ARE IN METRE	ES AOD UNLES				
	4. TI	HE DRAV	VING TO BE REA	D IN CONJUN				
	A	PPENDIC	TION FOR HIGH CES, DRAWINGS	NYKGDD-WSP	-SMN-ALL-I	DR-CB	-0001,	
			GDD-WSP-SMN- THE SCHEDULE			E DRA	WING	S
			WSP-SMN-STRO			I ALL		
			NS/LEVELS THA					ORKS
	EF	RRORS, T	HE CONTRACTO	OR NEEDS TO S				MC
	6. FC	OR THE A	AFFECTED AREAS	S PRIOR TO W				R
	SU	URVEYS T	TO POSITIVELY I US. REFER TO AI	DENTIFY AND	MARK-UP A	ANY U		
	IN	IFORMA	TION.		rokrokin	LN		
	-		DESIGNED ELEN		RAWING AF	RE INC	DICATIN	VE.
	V	VINGWA	LL DIMENSIONS EARTHWORK PE	AND SPLAY A	NGLES SHO	WN A	RE SUE	BJECT
	C	ONTRAC	TOR FOR THEIR	DESIGN.				
	P05 1	11/05/2023	UPDATED FOR AIP I	REVISION		SH	 DM	DM
	P05 1 Rev.	11/05/2023 Date	UPDATED FOR AIP 1	REVISION		SH By	DM	
				Description				
				Description				
		Date	/hite Rose Office Par	Description	ane, Leeds, LS	Ву	Chk'd	
		Date	/hite Rose Office Par	Description	ane, Leeds, LS	Ву	Chk'd	
		Date	/hite Rose Office Par	Description	ane, Leeds, LS	Ву	Chk'd	
	Rev.	Date	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire	By	Chk'd	
	Rev.	Date	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire	By	Chk'd	
	Rev.	Date	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire	By	Chk'd	
	Rev.	Date	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil	By	Chk'd	
	Rev.	Date	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil	By	Chk'd	
	Rev.	Date Three W	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil	By	Chk'd	
	Rev.	Date Three W itle	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION	Ву	Chk'd	
	Rev.	Date Three W itle	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION ERSION	Ву	Chk'd	
	Rev.	Date Three W itle	/hite Rose Office Par T+ 44 (0) 113 3	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION ERSION	Ву	Chk'd	
	Rev. Client Project Ti Drawing Scale	Date Three W	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION ERSION RT (STRO GEMENT 2	By	, UK	App'c
	Rev. Rev. Client Project Ti Drawing Scale AS S Original S	Date Three W itle Title A: SHOWN Size	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH Drawn JW Date	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION ERSION T (STRO GEMENT 2 Approved HM Date	Ву 111 ODL	, UK , UK Authorised HN Date	App'c
	Rev. Client Project Ti Drawing Scale AS S Original S A	Date Three W itle Title Title SHOWN Size 1	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION ERSION T (STRO GEMENT 2	Ву 111 ODL	Chk'd , UK Authorised HN Date 05/05	Арр'с Арр'с 4 Л 5/20
	Rev. Rev. Client Project Ti Drawing Scale AS S Original S	Date Three W itle Title Title SHOWN Size 1	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH Drawn JW Date 05/05/20	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION RT (STRO GEMENT 2 Approved HM Date 05/05/2	Ву 111 ODL	Chk'd , UK Authorised HN Date 05/05 Suitabilit	Арр'с 4 Л 5/20
	Rev. Client Project Ti Drawing Scale AS S Original S A Drawing S Drawing S	Date Three W Ittle Title CHOWN Size 1 Status	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH Drawn JW Date 05/05/20 FOR INFO	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION T (STRO GEMENT 2 Approved HM Date 05/05/2	ву 111 ODL	Chk'd , UK Authorised HN Date 05/05	App'd App'd 5/20
	Rev. Rev. Client Project Tri Drawing T Scale AS S Original S AS Drawing S Drawing S	Date Three W Ittle Title CHOWN Size 1 Status	/hite Rose Office Par T+ 44 (0) 113 3 A59 KEX 59 KEXGILI GENERAI SH Drawn JW Date 05/05/20	Description	ane, Leeds, LS 113 395 6201 rkshire ouncil ERSION RT (STRO GEMENT 2 Approved HM Date 05/05/2	By 111 ODL	Chk'd , UK Authorisec HN Date 05/05 Suitabilit Suitabilit	App'c App'c 5/20



Ш CA S Ó


Ζ Ο






- 19. 1.25M RAISED STONE WALLS ATOP CULVERT WINGWALLS AND HEADWALLS TO BE PROVIDED WHERE SHOWN ON STRUCTURE
- 20. ALL STONEWORK TO BE IN ACCORDANCE WITH APPENDIX 24/1 OF THE SPECIFICATION AND DETAILS SHOWN ON DRAWING

- 22. REDUNDANT EXCAVATED SITE ROCK AND WOODY DEBRIS TO BE RE-USED TO FORM THE 300 MIN THICK NATURAL WATERCOURSE BED WITHIN PRECAST BOX CULVERTS. IF SUFFICIENT MATERIAL IS NOT AVAILABLE, OR ADDITIONAL MATERIAL IS REQUIRED, THEN UNCONTAMINATED MATERIAL SUITABLY GRADED TO MATCH THE EXISTING WATERCOURSE BED SHOULD BE USED. ADDITIONAL MATERIALS TO BE AGREED WITH THE NEC4 PROJECT MANAGER 23. SCOUR PROTECTION AT INLETS AND OUTLETS TO BE PROVIDED WHERE SHOWN ON STRUCTURE SPECIFIC DRAWINGS AND IN ACCORDANCE WITH DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002.
- 24. TO ALLOW SAFE AND UNDISTURBED PASSAGE OF FISH (I.E.: BROWN TROUT LESS THAN 25CM AND COURSE FISH BETWEEN 25 - 50CM) FISH BAFFLES HAVE BEEN PROVIDED IN ACCORDANCE WITH THE ENVIRONMENT AGENCY FISH PASS MANUAL (GEHO 0910 BTBP-E-E: NOV. 2010) - SEE STRUCTURE SPECIFIC DRAWINGS FOR FURTHER
- 25. TO ALLOW SAFE AND UNDISTURBED PASSAGE OF OTTERS, MAMMAL LEDGES HAVE BEEN SPECIFIED - SEE STRUCTURE SPECIFIC 26. OTTER FENCING TO BE PROVIDED AS DETAILED ON STRUCTURE







NOTES GENERAL

ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE.

- ALL LEVELS ARE IN METRES AOD UNLESS NOTED OTHERWISE. DO NOT SCALE FROM THIS DRAWING.
- THE DRAWING TO BE READ IN CONJUNCTION WITH THE
- SPECIFICATION FOR HIGHWAY WORKS, CONTRACT SPECIFIC APPENDICES, DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002, AND WITH THE SPECIFIC DRAWINGS FOR EACH STRUCTURE
- THE CONTRACTOR SHALL MEASURE AND CONFIRM ALL DIMENSIONS/LEVELS THAT HAVE A DIRECT IMPACT ON THE WORKS PRIOR TO EXECUTION. IN CASE OF DOUBTS, OMISSIONS OR ERRORS, CONTRACTOR TO SEEK CLARIFICATION FROM THE NEC4 PROJECT MANAGER.
- FOR THE AFFECTED AREAS PRIOR TO WORKS THE CONTRACTOR SHALL OBTAIN UP-TO-DATE UTILITY PLANS AND CARRY OUT A SURVEYS TO POSITIVELY IDENTIFY AND MARK-UP ANY UTILITY APPARATUS. REFER TO APPENDIX 1/16 FOR FURTHER INFORMATION.
- ONTRACTOR DESIGNED ELEMENTS:
- THE CONTRACTOR IS RESPONSIBLE FOR DESIGNING THE PRECAST REINFORCED CONCRETE ELEMENTS LISTED IN ACCORDANCE WITH NYCC AIP DOCUMENTATION. SEE APPENDIX 1/10 FOR FURTHER DETAILS.
- UNLESS NOTED OTHERWISE EXTERNAL ARRISES AND INTERNAL CORNERS OF REINFORCED CONCRETE ELEMENTS TO HAVE MINIMUM 25 X 25 CHAMFER.
- EOTECHNICAL: FORMATION INSPECTIONS SHALL BE UNDERTAKEN BY THE NEC4 SUPERVISOR BEFORE COVERING WITH ANY PLACED MATERIAL. ANY SOFT SPOTS SHALL BE EXCAVATED AND REPLACED WITH WELL COMPACTED GRANULAR MATERIAL IN ACCORDANCE WITH SERIES 600 OF THE SPECIFICATION FOR HIGHWAY WORKS.
- .0. SEE STRUCTURE SPECIFIC DRAWINGS FOR CULVERT FOUNDATION AND BEDDING REQUIREMENTS.
- EMBANKMENT SLOPES WHERE THEY INTERFACE WITH INLETS AND OUTLETS TO BE OF A MAXIMUM OF 1 IN 3. .2. PRECAST BOX CULVERT TO BE BACKFILLED WITH 6N OR 6P
- STRUCTURAL FILL IN ACCORDANCE WITH SERIES 600 OF THE SPECIFICATION FOR HIGHWAY WORKS OVER EXTENTS SHOWN ON STRUCTURE SPECIFIC DRAWINGS. WATERPROOFING AND DRAINAGE:
- 3. BURIED CONCRETE ELEMENTS SHALL BE PAINTED WITH 2 COATS OF CUT BACK BITUMEN IN ACCORDANCE WITH SPECIFICATION CLAUSE 2004 & 2006, WITH THE EXCEPTION OF AREAS TO RECEIVE A WATERPROOFING MEMBRANE.
- 4. SURFACES TO RECEIVE WATERPROOFING MEMBRANE TO HAVE U4 FINISH IN ACCORDANCE WITH SERIES 1700 OF THE SPECIFICATION FOR HIGHWAY WORKS. WATERPROOFING MEMBRANE TO BE IN ACCORDANCE WITH APPENDIX 20/1 OF THE SPECIFICATION AND DETAILS SHOWN ON DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002.
- 5. WEEPHOLES TO BE PROVIDED TO CULVERT WINGWALLS IN ACCORDANCE WITH THE DETAILS SHOWN ON DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002.
- MANHOLE ACCESS:
- 16. MANHOLE ACCESS TO BE PROVIDED AS DETAILED ON STRUCTURE SPECIFIC DRAWINGS. TIMBER FENCING:
- 17. TIMBER POST AND RAIL FENCING TO BE INSTALLED AS SHOWN ON STRUCTURE SPECIFIC DRAWINGS AND IN ACCORDANCE WITH DRAWING NYKGDD-WSP-SMN-ALL-DR-CB-0002

FETY, HEALTH AND ENVIRONMENTAL INFORMATION

ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS RAWING, NOTE THE FOLLOWING SIGNIFICANT RESIDUAL RISKS NSTRUCTION

EF 004 - WORKING IN CONFINED SPACE F 006 - BACKFILLING OF THE STRUCTUR EE 007 - WORKING WITH LIETING PLANT DURING INSTALLATION OF PRECAST LINIT 009 - DAMAGE TO EXISTING STATUTORY SERVICES

AFETY, HEALTH AND ENVIRONMENTAL SYMBOL LEGEND INDICATES A RESIDUAL RISK AS A WARNING

P07	15/05/2023	UPDATED FOR AIP REVISION	SH	DM	DM
Rev.	Date	Description	Ву	Chk'd	App'd

Three White Rose Office Park, Millshaw Park Lane, Leeds, LS11 0DL, UK T+ 44 (0) 113 395 6200, F+ 44 (0) 113 395 6201 wsp.com




A59 KEX GILL DIVERSION

TYPICAL CULVERT DETAILS SHEET 1 OF 2

awing Title

Scale	Drawn	Checked	Approved	Authorised
AS SHOWN	LS	IM	НМ	HM
Original Size A1	~		Date 31/10/20	Date 31/10/20
Drawing Status	Suitability			
	FOR INFO	RMATION		S2
Drawing Number Project	Originato	r İ Volu		S2 Project Ref. No.
Drawing Number				



CA S <u>N</u> Ю

-	INDICATIVE FINISHED EARTHWORK PROFILE

NOTE: EXPOSED NUTS AND WASHERS TO BE COATED IN TAPE MADE FROM NON-WOVEN SYNTHETIC FIBRE FABRIC, IMPREGNATED AND COATED WITH A NEUTRAL COMPOUND BASED ON SATURATED PETROLEUM HYDROCARBONS AND INERT SILICEOUS FILLERS (E.G.: DENSO TAPE OR APPROVED SIMILAR). FULL ARRANGEMENT BELOW GROUND, INCLUDING POST, TO BE PAINTED IN

20 X 20 POLYSULPHIDE SEALANT (COLOUR TO MATCH STONEWORK) IN ACCORDANCE WITH CLAUSE 2303 OF SHW

20 X 20 POLYSULPHIDE SEALANT (COLOUR TO MATCH STONEWORK) IN ACCORDANCE WITH CLAUSE 2303

20 X 20 POLYSULPHIDE SEALANT (COLOUR TO MATCH STONEWORK) IN ACCORDANCE WITH CLAUSE 2303 OF SHW

NOTE: EXTERNAL SIDE JOINTS NOT COVERED WITH WATERPROOFING MEMBRANE TO HAVE JOINT SYSTEM COMPATIBLE CUT-BACK BITUMEN. JOINT SHOULD BE ROBUST ENOUGH TO PREVENT STRUCTURAL BACKFILL FROM ENTERING JOINTS DURING BACKFILLING.



WATERTIGHT JOINT COMPATIBLE WITH CHOSEN WATERPROOFING MEMBRANE AND EXPECTED MOVEMENT AT JOINTS **BASED ON CONTRACTOR'S** DESIGN. JOINT TO EXTEND DOWN CULVERT WALLS TO MATCH WATERPROOFING MEMBRANE EXTENTS

N	от	ΈS		
c	EN	FD	۸ı	

ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE

THE DRAWING TO BE READ IN CONJUNCTION WITH THE

SPECIFICATION FOR HIGHWAY WORKS, CONTRACT SPECIFIC

TIMBER POST AND RAIL FENCING TO BE INSTALLED AS

1.25M RAISED STONE WALLS ATOP CULVERT WINGWALLS AND

ALL STONEWORK TO BE IN ACCORDANCE WITH APPENDIX 24/1

SH DM

By Chk'd App'd

OTTER FENCING TO BE PROVIDED AS DETAILED ON

HEADWALLS TO BE PROVIDED WHERE SHOWN ON

SHOWN ON STRUCTURE SPECIFIC DRAWINGS.

TIMBER FENCING:

ALL LEVELS ARE IN METRES AOD UNLESS NOTED OTHERWISE.

DO NOT SCALE FROM THIS DRAWING.

NYKGDD-WSP-SMN-ALL-DR-CB-0001

STRUCTURE SPECIFIC DRAWINGS.

STRUCTURE SPECIFIC DRAWINGS.

STONE FACING AND STONE WALLS:

OF THE SPECIFICATION.

P07 15/05/2023 UPDATED FOR AIP REVISION

Date

oject Title

rawing Title

AS SHOWN

riginal Size

Α1

awing Status

rawing Number

NYKGDD

ALL

Description

\\SD

Three White Rose Office Park, Millshaw Park Lane, Leeds, LS11 0DL, UK

T+ 44 (0) 113 395 6200, F+ 44 (0) 113 395 6201

wsp.com

A59 KEX GILL DIVERSION

TYPICAL CULVERT DETAILS

(SHEET 2 OF 2)

IM

18/05/20

НМ

18/05/20

Date

Volume

0002

Number

SMN

HM

18/05/20

S2

Project Ref. No

P07

Revision

Suitability

LS

18/05/20

FOR INFORMATION

CB

Type Role

Originator

WSP

DR

North Yorkshire

County Council


APPENDICES, AND DRAWING

Appendix D

IDEALISED DIAGRAM

CONFIDENTIAL | WSP

NSD



A59 KEX GILL CULVERT (STRUCTURE no.5) IDEALISED STRUCTURE FOR 2D PLANE FRAME

Appendix E

DESIGNERS RISK ASSESSMENT

CONFIDENTIAL | WSP

110

BMS: Project Delivery

T446: Design Risk Management Schedule	Project No	70049554	Project Name	A59 KEX GILL DIVERSION - A59 Kex Gill Culvert (STR005)

Guidance Notes (see guidance notes page for more details)

Design risk management should be an integral part of the overall design development and designers should think of it in terms of considering constructability, etc. Designers only need to document their consideration of risks in this simple risk management schedule format. There is no requirement for quantative design risk assessments to be carried out/documented and these should be avoided

* Risks should be considered in a logical sequence relating to the location/operational environment, constructability/installability, operability (normal/emergency), maintainability (inc routine cleaning, replacement, etc.), and alteration/decommissioning/dismantling/demolition, and should be categorised against those headings, CIRIA guidance documents C755, C756, C686, C607, etc. provide a useful checklist and detailed guidance on the identification of risks to be considered during design and how those risks might be addressed - see detailed guidance notes for more details § Significant residual risks are those which are unusual, not obvious, difficult to manage, or where critical design assumptions apply. The documentation by designers of residual risks that cover well-known and understood hazards should be avoided.

Ref	Risk Category* & Phase where appropriate, e.g. location/environment, construction, operation, maintenance, alteration/demolition	Work Element/Location (where appropriate)	Hazard or Risk Issue Identified	Risk Management Owner	Design ERIc Action Required (e.g. hazard elimination/risk mitigation action, information to be provided to others)		Design Action Status/Final (e.g. traceability of ERIc act significant residual risk, crit
001	Design	(STR005)	Handling of large volumes of concrete including erection of shuttering which requires significant temporary works. Large reinforcement cages also introduces risks associated with impaling/ heavy lifting of bars, working at heights etc.	Designer	Prefabricated/precast structural units have been selected to eliminate insitu works and associated temporary works.	None.	None.
002	Design	A59 Kex Gill Culvert (STR005)	Presence of protected species of wildlife.	Designer	Ecology survey to be carried out prior to works to determine presence of any protected flora/fauna within the area. Provision of mammal ledges, fish baffles etc. within structure to be confirmed.		Designer to highlight any sy design drawings.
003	Design/ Construction	(STR005)	Existing infrastructure capability to take heavy goods vehicles for materials and plant import & export to site. Damage to infrastructure/vehicles if infrastructure deteriorates.	Designer / Contractor	Designer shall assess any affected existing structures on the scheme with a view to identifying if strengthening/modification work needs to be carried out as part of the scheme. Prefabricated/precast structural elements shall be sized to ease their transportation along existing infrastructure network. Local Authority to be informed of any abnormal loads to be transported to site well in advance of their delivery to enable careful planning. Contractor to carefully plan all delivery routes.		Designer shall show weight elements on design drawin abnormal loads. Any specific structural requ structures) to be communi any construction work beir
004	Design / Construction / Operation		Size of culvert stucture opening creating confined space working on site.	Designer / Contractor / Maintainer	Sizing of culvert dictated by flood/drainage model analysis. Where possible, dimensions of culvert shall be increased to allow greater working space inside the structure.	Only trained site personnel to be allowed entry and working within a confined space including correct PPE and apparatus. Contractor to confirm and set up a safe system of working during construction as well as future maintenance activities.	Confined space working sh design drawings.
005	Design/ Construction	A59 Kex Gill Culvert (STR005)	Unknown ground conditions.	Designer / Contractor	Design to take into account the results of the ground investigation. Geotechnical Engineers to conduct sensitivity analysis where uncertainty exists.	None.	Ground Investigation Report take account of anticipated
006	Construction	A59 Kex Gill Culvert (STR005)	Backfilling of box culvert structure.	Designer / Contractor	Backfilling of the structure shall be carried out in a staged manner to avoid imbalance of fill pressures. Maximum differential fill height between each box wall shall be limited to 0.5m.	None.	Backfilling procedure to be drawings.
007	Construction		Working with lifting plant during installation of precast units.	Designer / Contractor	Temporary works design to be carried out by a competent contractor including independent design check. Geotechnical designer to confirm proposed methods of working in relation to location of temporary footings for the crane. Areas of loose material to be confirmed in the GI.	Contractor to confirm and set up a safe system of working during construction activities. Temporary works contractor is responsible for providing a certified temporary works design.	Designer to highlight any sy requirements on design dra
008	Construction		Instability/collapse of temporary works supporting excavations.	Contractor	Temporary works design to be carried out by a competent contractor including independent design check. Geotechnical designer to confirm proposed methods of working and adequacy of temporary works design. Areas of loose material to be confirmed in the GI. Any overdig to be approved by geotech team prior to works being carried out.		Designer shall highlight any requirements on design dra



inal Resolution Notes action, communication of critical design criteria, etc.)	Significant Residual Risk [§]	Date Logged/ Reviewed	Raised By
	No	01.10.19	Imtiaz Mulla
y special ecological features on	No	01.10.19	Imtiaz Mulla
ight of all significant structural wings and clearly identify any equirements (existing unicated to contractor prior to being carried out.	No	01.10.19	Imtiaz Mulla
shall be identified on all	Yes	01.10.19	Imtiaz Mulla
eport to be provided. Design to ated ground conditions.	No	01.10.19	Imtiaz Mulla
be detailed on all design	Yes	01.10.19	Imtiaz Mulla
y special temporary works drawings.	Yes	01.10.19	Imtiaz Mulla
any special temporary works drawings.	No	01.10.19	Imtiaz Mulla

BMS: Project Delivery

T446: Design Risk Management Schedule	Project No	70049554	Project Name	A59 KEX GILL DIVERSION - A59 Kex Gill Culvert (STR005)
с с				

Guidance Notes (see guidance notes page for more details)

Design risk management should be an integral part of the overall design development and designers should think of it in terms of considering constructability, etc. Designers only need to document their consideration of risks in this simple risk management schedule format. There is no requirement for quantative design risk assessments to be carried out/documented and these should be avoided

* Risks should be considered in a logical sequence relating to the location/operational environment, constructability/installability, operability (inc routine cleaning, replacement, etc.), and alteration/decommissioning/dismantling/demolition, and should be categorised against those headings, CIRIA guidance documents C755, C756, C686, C607, etc. provide a useful checklist and detailed guidance on the identification of risks to be considered during design and how those risks might be addressed - see detailed guidance notes for more details § Significant residual risks are those which are unusual, not obvious, difficult to manage, or where critical design assumptions apply. The documentation by designers of residual risks that cover well-known and understood hazards should be avoided.

Ref	Risk Category* & Phase where appropriate, e.g. location/environment, construction, operation, maintenance, alteration/demolition	Work Element/Location (where appropriate)	Hazard or Risk Issue Identified	Risk Management Owner	(e.g. hazard elimination/risk mitigation action, information to be provided to others)	Requirements/Management Arrangements and/or		Significant Residual Risk [§]		Raised By
09	Construction	A59 Kex Gill Culvert (STR005)	Damage to existing statutory services.	Contractor		contractor. Contractor to locate all services using hand tools before mechanical excavation can	Designer to highlight location of any statutory services on design drawings.	Yes	01.10.19	Imtiaz Mulla
10	•	A59 Kex Gill Culvert (STR005)	Working at height.	Contractor / Maintainer	reduce activities carried out at height.	Contractor to confirm and set up a safe system of working during construction as well as inspection/maintenance activities.	None.	No	01.10.19	Imtiaz Mulla
11		A59 Kex Gill Culvert (STR005)	Working near an existing watercourse.	Contractor / Maintainer	construction works.	Only trained site personnel to be allowed entry and working within a confined space including correct PPE and apparatus. Contractor to confirm and set up a safe system of working during construction as well as inspection/maintenance activities.	Design flood level to be identified on drawings.	No	01.10.19	Imtiaz Mulla
12		A59 Kex Gill Culvert (STR005)	Working near live traffic.	Contractor / Maintainer	Identify access/exit location of construction traffic. Where required, determine and set up traffic management prior to works commencing. Contractor to conside delivery of materials/plant during off- peak traffic hours. Wheel washing facility to be used on site to minimise mud tracked onto existing road network.	Contractor to confirm and set up a safe system of working during construction as well as inspection/maintenance activities.	None.	No	01.10.19	Imtiaz Mulla

Copy rows then insert above this line to ensure formula are copied



Issue 3.0

Appendix F

CULVERTS FEASIBILITY STUDY

CONFIDENTIAL | WSP

110



TECHNICAL MEMO

то	North Yorkshire Country Council	FROM	Imtiaz Mulla				
DATE	12 September 2019	REVIEWED	Hitan Mistry				
		APPROVED	Philip Santos / David Wilson				
		CONFIDENTIALITY	Internal				
SUBJECT	BJECT A59 Kex Gill Diversion – Culvert Feasibility Report_P02						

Background

The A59 provides a key strategic east-west connection in North Yorkshire, linking Harrogate and Skipton.

The A59 at Kex Gill passes through a rural and open landscape, designated as the Nidderdale Area of Outstanding Natural Beauty (AONB). In addition, large parts of the area are designated as Site of Special Scientific Interest (SSSI), Special Protection Area (SPA) and Special Area of Conservation (SAC).

There is a long history of landslips around this location. These landslips deposit material onto the road leading to unpredictable closures of the A59. Analysis of existing geotechnical information indicates that the primary cause of these landslips is heavy rainfall, coupled with relatively unstable land on the hillside slopes, leading to earthwork failures. The most recent landslip occurred in May 2018, and has resulted in a road closure for several weeks. In addition, the cost to North Yorkshire County Council (NYCC) for emergency slope stabilisation and associated carriageway work are becoming significant with an estimated £1.6million expenditure to date (this figure excludes the most resent May 2018 closure).

Proposed Alignment

Various studies, site investigations, consultation events and the production of reports, such as the Option Appraisal Report, have resulted in the determination of the preferred new A59 road realignment. Detail design of this preferred realignment is now being developed and shall affect 5 existing structures as well as include proposals for 11 new structures as listed below with requirements for further structures to be confirmed as the design is developed:

- 3No. Existing Culverts
- 2No. Existing Bridges
- 2No. Proposed Underpasses
- 8No. Proposed Culverts
- 1No. Proposed Retaining Wall
- 1No. Proposed open channel watercourse

Refer to the scheme structure location plan in Appendix A for further details.

Report Objective

WSP has been commissioned to progress the Detailed Design of the A59 Kex Gill Diversion, including modifications to North Moor Road and Church Hill Junctions. The scheme involves diverting the existing 2-lane single carriageway and including provision for a climbing lane in the westbound direction.

To accommodate diversion to the proposed A59 alignment, 3 existing culvert structures shall be affected, and 8 new culverts shall be required. The proposed culverts will carry existing watercourses beneath the road and bridleway crossings. This technical memo has been prepared to assess structural forms for the proposed culvert structures throughout the scheme. A summary of the aforementioned structures are listed in table 1:

REFERENCE	NEW / EXISTING	MAINLINE CHAINAGE	LOCATION	APPROX. LENGTH (M)	INTERNAL WIDTH (MM)	INTERNAL HEIGHT (MM)
Structure A	Existing culvert to be removed	2+596 to 2+620	NORTH MOOR ROAD	32	2no. 700 dia. circular concrete pip	
Structure No.1	New	2+582 to 2+686	A59 MAINLINE	104	2100	1700
Structure No.3	Existing to be retained	2+985	A59 MAINLINE	189	700 dia. circula	ır concrete pipe
Structure No.5	New	4+085	A59 MAINLINE	60	1000	1400
Structure No.7	New	5+440	PROPOSED HALL BECK BRIDLEWAY	9.5	3300	1950
Structure No.8	New	5+525 to 5+645	A59 MAINLINE	121	3900	2125
Structure B	Existing culvert to be removed	5+880	A59 MAINLINE	9	Circa. 900 x 9	00 stone arch
Structure No.9	New	5+880	A59 MAINLINE	60	2100	2250
Structure No.10	New	6+028 to 6+089	HALL LANE	61	4200	2550
Structure No.11	New	2+615	NORTH MOOR ROAD	15	1050 dia. circular concrete pipe	
Structure No.12	New	6+095	A59 MAINLINE	60	900 dia. circular concrete pipe	

Table 1 – Culvert Structure Details



Existing Culverts

There are 3 existing culverts which will be directly impacted by the proposed A59 diversion alignment.

Structure A is culvert structure approximately 32m long with 2no. 700mm diameter circular concrete pipes carrying Hall Beck under North Moor Road at the existing A59 junction. The inlets/outlets are located either side of the road with dry stone headwalls to both openings. The eastern headwall has an additional 3no. circular pipes of 150mm, 250mm & 550mm diameters and the western headwall has an additional 1no. circular pipe of 300mm diameter all of which outfall into Hall Beck. There are no structural records confirming the structure's current condition. As part of the scheme, this structure is to be removed and replaced with a single culvert structure no.1 which will carry the watercourse beneath both North Moor Road as well as the re-aligned A59.





Structure 3 is a 700mm diameter concrete pipe culvert approximately 189m long which carries a watercourse with an inlet located to the north of North Moor Road and an outlet located in between the quarry access track and north of the existing A59. Headwalls are unavailable but there is a manhole located approximately at the halfway point of the culvert. There are no structural records of the structure, however NYCC provided details of a CCTV survey carried out on the culvert on 19.02.19. The survey confirmed the concrete pipe culvert to be in fair condition with only minor cracking noted. It was also confirmed there were no additional pipe connection outlets into the culvert from the surrounding area. As part of the scheme, this culvert is to be retained and any proposed works to this structure will be confirmed at detail design stage.



Structure B is a circa. 900mm x 900mm stone arch culvert approximately 9m long which carries Cote Hill Dike under the existing A59. It has an inlet/outlet located either side of the road with stone & mortar headwalls to both openings. There are no structural records confirming the structure's current condition. As part of the scheme, this culvert is to be removed and replaced with culvert structure no.9 which will carry the watercourse beneath the re-aligned A59.





Proposed Culverts

As part of the scheme, 8no. new culvert structures are proposed to maintain flow of the existing watercourses. Requirements for these structures has been largely dictated by the flood/drainage model of the project catchment area. The modelling works carried out by WSP to date has been able to determine design flood levels, expected water flows as well as approximate sizing of the culverts. Details of the flood/drainage model including methodology and design assumptions are contained within the flood/drainage model report. Refer to the scheme structure location plan in Appendix A for further details.

DESIGN CONSIDERATIONS

The following assumptions/constraints, have been considered when assessing structural forms for the proposed culvert structures:

- Provision cost effective/simple solutions.
- Minimise land take to ensure this is as low as reasonably practical.

wsp

- Foundation requirements (ground bearing, piles etc.) shall be based on the ground profile at each discreet structure location.
- Sizing of the culverts to ensure ease with their associated future inspection and maintenance as well as future increase in capacity.
- Ensure disruption to local environment is as low as reasonably practical.
- Statutory services potentially impacting the works shall be protected or diverted accordingly.
- Gradient of the highway embankments are currently based on the provision of 1:3 slopes.
- A proprietary timber post and rail fence shall be provided on the headwall/wingwall at the culvert openings
- Sourcing materials from local sources to minimise transportation requirements.
- Ensure construction can be carried out in a safe and efficient manner. Consideration was given to utilising precast elements which could be delivered and installed quickly thereby reducing insitu works.
- Provision of aesthetic details such as cladding fascia (masonry, stonework etc.) to the culvert openings is still to be confirmed. There is scope to re-use stonework from the 2 existing culverts which are proposed to be removed. Liaison with Key stakeholders (NYCC Heritage team and AONB/Natural England) is currently under progression.
- An Ecology survey carried out by WSP on 22nd/23rd May 2019, confirmed mammal ledges and fish baffles will be required to be accommodated within structure no. 8, 9 & 10 only.
- Requirements for any additional hydraulic features (flow control mechanisms, scour protection, plunge pools etc.) shall be confirmed during the detail design.

STRUCTURE TECHNICAL APPROVALS

Current DMRB requirements for structures (BD 2/12) states any culvert with an internal diameter of less than 900mm does not constitute a 'structure'. This means that it would not be required to go through a structure technical approval process and would instead go through the relevant drainage TAA process.

Design of the proposed culverts identified in this memo will be subject to a structure technical approval process. All other proposed drainage pipes, channels etc. required as part of the scheme (<900mm dia.) will be subject to drainage design only.

STRUCTURAL FORM OPTIONS CONSIDERED

The following structural options for the proposed culverts have been considered:

- Option A Precast Concrete Box
- Option B Corrugated Steel Pipe
- Option C Insitu Concrete Portal
- Option D Precast Concrete Pipe

This memo provides a high-level overview of the above. A recommendation is also provided regarding the option considered most feasible at each of the 8 proposed structure locations. Refer to options sketches in Appendix B for further details.



OPTION A – PRECAST CONCRETE BOX

Option A comprises a Precast Concrete Box solution and details of its advantages & disadvantages are tabulated below:

Table 2 – Option A: Precast Concrete Box

OPTION A	PRECAST CONCRETE BOX			
ADVANTAGES	Fabrication of box units in a controlled environment ensures a high-quality surface finish can be achieved. Units are cast in the factory under comprehensive quality control eliminating the drawbacks imposed by weather and site conditions.			
	 Precast box units can be manufactured in a variety of bespoke internal profiles and sizes. 			
	 Precast box units are most cost effective compared to cast insitu concrete boxes which require temporary works and more labour which increases construction programme time. 			
	 Speed/ease of installation – can be easily positioned in shallow or deep filled installations. 			
	 Precast box units can be delivered to site and installed thereby reducing on site works. 			
	Temporary diversion of watercourse is minimised due to rapid installation.			
	Concrete does not require additional treatments to prolong their life or improve performance. The surface will not rust and the smooth internal finish ensures optimum flow of water through the structure.			
	Minimum maintenance liability (compared to equivalent steel structure).			
	Loading can be applied onto the box units as soon as they are installed.			
DISADVANTAGES	 Lifting of heavy box units into position may require use of large craneage which may not be practical on a constricted site. 			
	 Box unit sizes are limited as there is an upper limit to what can practically be fabricated in the factory and delivered to site. 			
	 Transportation costs are increased if location of the fabrication factory is some distance from the construction site. 			



OPTION B – CORRUGATED STEEL PIPE

Option B comprises a Corrugated Steel Pipe solution and details of its advantages & disadvantages are tabulated below:

Table 3 – Option B: Corrugated Steel Pipe

OPTION B	CORRUGATED STEEL PIPE
ADVANTAGES	Amount of temporary works required compared to insitu concrete is significantly less and thereby expedites construction programme.
	Sections forming the pipe can be delivered to site as sheets and be installed on site by lifting into position and splicing.
	Speed/ease of installation – can be easily positioned in shallow or deep filled installations.
	Temporary diversion of watercourse is minimised due to rapid installation.
	Pipes can be manufactured in a variety of bespoke internal profiles and sizes.
	Due to their lighter weight, transportation costs associated with delivering steel sheets forming the pipe are less compared to their similar concrete counterparts since they are much lighter.
	Lifting of steel sheets into position to fabricate the pipe will require use of smaller craneage compared to lifting precast concrete units.
	Due to their flexibility, steel pipes can withstand ground settlements much more effectively than concrete sections which are prone to cracking.
DISADVANTAGES	Steel pipes require additional corrosion protective treatments to prolong their life otherwise they will deteriorate. This is an additional maintenance item to be addressed during its design life and hence an additional cost.
	 Loading onto the pipe cannot be applied until the structure is completely backfilled.
	Temporary works is still required when fabricating pipe sections.
	 Waterproofing around pipe is still required.
	Pipe joint connections susceptible to failure during its design life if not installed correctly.
	 Staged method of backfilling is required to ensure the pipe does not suffer premature warping.



OPTION C – INSITU CONCRETE PORTAL

Option C comprises an Insitu Concrete Portal solution and details of its advantages & disadvantages are tabulated below:

Table 4 – Option C: Insitu Concrete Portal

ed to precast concrete ieved as the structure
ieved as the structure
concrete to site.
l profiles and sizes.
o prolong their life or d the smooth internal ucture.
ent steel structure).
) to cast concrete and pared to precast units.
ntil the concrete has
site and workmanship
ons.
ary diversion of the



OPTION D – PRECAST CONCRETE PIPE

Option D comprises a Precast Concrete Pipe solution and details of its advantages & disadvantages are tabulated below:

Table 5 – Option D: Precast Concrete Pipe

OPTION D	PRECAST CONCRETE PIPE				
ADVANTAGES	Fabrication of pipe units in a controlled environment ensures a high-quality surface finish can be achieved. Units are cast in the factory under comprehensive quality control eliminating the drawbacks imposed by weather and site conditions.				
	Precast pipe units can be manufactured in a variety of sizes.				
	 Precast pipe units are most cost effective compared to cast insitu concrete which require temporary works and more labour which increases construction programme time. 				
	 Speed/ease of installation – can be easily positioned in shallow or deep filled installations. 				
	Temporary diversion of watercourse is minimised due to rapid installation.				
	Concrete does not require additional treatments to prolong their life or improve performance. The surface will not rust and the smooth internal finish ensures optimum flow of water through the structure.				
	Minimum maintenance liability (compared to equivalent steel structure).				
	Loading can be applied onto the pipe units as soon as they are installed.				
DISADVANTAGES	 Lifting of heavy pipe units into position may require use of large craneage which may not be practical on a constricted site. 				
	 Transportation costs are increased if location of the fabrication factory is some distance from the construction site. 				
	Pipe units will still require insitu concrete bedding foundations to be cast prior to their installation.				
	 Has a lower hydraulic capacity compared to its equivalent sized box shaped unit. 				

Geotechnical Information

EXISTING GROUND CONDITIONS

A Geotechnical Design Report is not yet available for the project and will be prepared following completion of all design elements. The GDR will define suitable parameters for the design and acceptable solutions. Table 1 below provides a summary of ground conditions anticipated at the 8 new culvert locations. This is based on data acquired from the 2017, 2018 & 2019 ground investigations. There may be variations in the ground conditions, and a worse case ground model will be assumed. Refer to the scheme structure location plan in Appendix A for borehole locations.

Table 6 – Anticipated ground conditions at the proposed culvert locations

CULVERT	GROUND CONDITIONS	BOREHOLE REF.
STRUCTURE NO.1	Soft to stiff sandy slightly gravelly clay of highly weathered mudstone and sandstone between 1.05m and 3.0m thickness overlying 2.8m to 5.55m of extremely weak to weak laminated mudstone overlying 0.98m to 3.2m of very weak to medium strong sandstone. This in turn overlies another layer of extremely weak to very weak mudstone with a thickness of 0.43m to 2.15m which overlies medium strong sandstone varying from 1.6m to an unproven thickness. The 1.6m thick sandstone is underlain by unproven extremely weak to very weak mudstone.	BH 61/17 & BH 101/18
STRUCTURE NO.5	A thin layer of peat (0.4m to 0.5m thickness) overlying highly weathered bedrock reduced to a slightly sandy slightly gravelly clay and sand with a recorded thickness of 0.2m to 1.6m overlying 3.9m of extremely weak to strong coarse sandstone which in turn overlies a very weak thinly laminated silty mudstone of unproven depth.	BH 24/17 & BH 25/17
STRUCTURE NO.7	Anticipated ground at this location is approximately 2.0m of soft slightly sandy clay (alluvium) overlying the highly weathered bedrock reduced to a slightly clayey very sandy gravel and a stiff sandy slightly gravelly clay to unproven depth. No ground investigation data is available at this location.	BH 46/17 & BH 111/18
STRUCTURE NO.8	Alluvium comprising soft slightly sandy slightly gravelly clay ranging in thickness between 4.45m to over 5.5m overlying weak to medium strong medium to coarse grained sandstone with a thickness of 2.2m which in turn overlies very weak to weak mudstone to unproven depth.	BH 115/18 & BH 120/18
STRUCTURE NO.9	Anticipated soft slightly clayey sand (alluvium) over highly weathered bedrock reduced to a firm to stiff slightly sandy slightly gravelly clay and sand. No ground investigation data is available at this location.	BH 54/17 & BH 55/17
STRUCTURE NO.10	Soft clay and soft sandy gravelly clay (alluvium) between 2.65m and 4.4m thick overlying 1.0m of weathered bedrock of gravelly clayey cobbles of sandstone and mudstone. This in turn overlies alternating layers of weak to strong, fine to coarse sandstone between 0.55m to 1.9m thick and extremely weak to weak mudstone between 0.6m and 1.5m thick. Unproven weak to strong sandstone was encountered at 4.05m BGL in BH56/17.	BH 56/17 & BH 121/18
STRUCTURE NO.11	Refer to ground conditions for structure no.1 as above.	BH 61/17 & BH 101/18
STRUCTURE NO.12	Soft clay and soft sandy gravelly silty clay (alluvium) between 0.4m and 6.0m thick overlying 0.3m of weak to medium strong fine-grained sandstone. This in turn overlies 0.86m of extremely weak to very weak mudstone which overlies 1.5m of medium strong sandstone overlying unproven very weak to medium strong mudstone and siltstone.	BH 55/17 & BH 57/17



RISKS ASSOCIATED WITH CULVERT WORKS

The geotechnical risks for the wider site are detailed below in Table 7. These risks have been reviewed and further assessed in the 'Live' Project Risk Registers.

Table 7 – Geotechnical risks of the proposed culverts

RISK CAUSE	RISK EVENT	PRIMARY RISK IMPACT	RISK RATING
ENGINEERING PROPERTIES	Risk that the ground model and associated engineering properties are worse than anticipated.	твс	Low - medium
INSTABILITY OF EXISTING EARTHWORKS	Failure of earthworks may impact or undermine the proposed culvert structures. Failure of culverts may impact existing or proposed earthworks.		Low - medium
GROUNDWATER	Risk that the ground water profile is worse than that identified on site.	ТВС	Low - medium
CONTAMINATED SOILS	Risk of unknown / unidentified contaminated soils.	ТВС	Low
INSTABILITY CAUSED BY SHALLOW MINE WORKINGS	Risk that the culvert would be impacted by unknown mine workings which may require grouting during construction phase.	ТВС	Low
CONSTRUCTABILITY OF CHOSEN CULVERT SOLUTION	Risk that the proposed culvert structures are no longer suitable due to the uncertainty of the ground model such as the rockhead being at a higher elevation, deeper alluvium, boulders and other obstructions being present.	твс	Medium
UNEXPLODED ORDNANCE (UXO)	The site is located within an area of low risk.	твс	Very low
BURIED SERVICES	Encountering buried services during excavation.	ТВС	Low



High Level Option Appraisal

As all the culvert structures are buried with limited access, any extensive maintenance works required to be carried out during their design life will be challenging. On this basis, concrete solutions are generally preferred over their steel counterparts due to their lower overall maintenance liabilities.

The smaller internal dimensions of structure no. 1 and 5 lend themselves to selection of a prefabricated solution. An insitu concrete option would require temporary formwork and a corrugated steel pipe option would require segments to be spliced together. Both these options would involve significant confined space working which would expose the labour force to additional health and safety risks during their construction. A precast concrete box (option A) would be the most appropriate solution for structure no. 1 and 5 as it would remove the risk of confined space working as well as simultaneously expediting their construction.

Structure no. 11 serves flows coming in from 2 open channel drainage ditches and outfalls into structure no.1 which in turn carries the water beneath the proposed A59. It shares a physical connection with structure no.1. Due to its relatively short 15m length and internal size, a precast concrete pipe (option D) would be the most suitable solution. The concrete pipe (structure no.11) would terminate into a bespoke insitu concrete segment (structure no.1) constituting a box with a circular cut-out to the wall to enable the pipe to be received.

At the eastern end of the project catchment up to existing Hall Lane junction, borehole data identified a large area of alluvium present up to 6m below existing ground level. The proposed A59 highway alignment runs through this area with structures no. 7, 8, 9, 10 & 12 due to be located in this section (refer to figure 3).




Figure 3 – Plan showing proposed A59, proposed structures and approximate area of existing alluvium (identified as the zone within the red line; circa 0.066km² / 66,000m²)



As alluvium is considered to be soft material, the risk of ground settlement is likely to be high unless some form of ground improvement is carried out. To put this into context, expected settlements under the max 8.5m high highway embankment are going to be in the order of 550mm if no piling or ground improvement is carried out. Settlements under the culvert structures will be less but conservative estimates are in the region of around 380mm based on 2.5m clear internal height of the culvert. Therefore, the culvert structures will not work without pile foundations or some other alternative form of ground improvement.

A number of ground improvement options were considered which are summarised below:

1. Piled embankment with a load transfer platform

This method would involve insertion of numerous driven pre-cast concrete piles into the existing ground with pilecaps and geogrid membrane tied together creating a load transfer platform. The highway embankment can then be built on top of the platform. Residual settlements would likely be within manageable limits without negatively impacting construction programme. This option is a well-established approach covered by standards (BS 8006-1) and offers the high degree of confidence in buildability, programme, and performance of the finished works. To maintain compatibility with the piled embankment, all culvert structures would also need to be constructed on piled foundations.

2. Partial dig out and replacement of Alluvium say to 2m below ground level

This would still leave a residual settlement of approximately 370mm below the embankment or 250mm below the culvert. In the absence of verification through detailed analysis, long term stability of the culvert structures are likely to be questionable. Costs of disposal of excavated material and import of granular fill are likely to exceed the costs of the piled option.

3. Full depth dig out and replacement of Alluvium with Structural Fill

This will require excavation to around 6m depth mostly below ground water level. This is doable but costly and will create a huge fill surplus plus requirement for import of granular material. Costs of disposal of excavated material and import of granular fill are likely to substantially greater than the costs of the piled option. It is likely to have substantial environmental impacts such as loss of woodland etc. It should however eliminate most of the settlement and overall ground stability should be good.

4. Deep Soil Mixing

Stabilisation of the soft ground by mixing with cement/lime. This option is costly but will deal with the settlement and stability issues. The earthworks balance would remain largely as existing however there would be environmental impacts associated with the use of cement. This is a proprietary process with a limited number of suppliers. It is possible that this option may be offered by tenderers as a value engineering option and may be considered if costs are favourable and performance similar to piled foundations can be demonstrated.

5. Vibro Stone Columns

This option is considered more cost effective than deep soil mixing but ruled out on the basis of the low strength of Alluvium may prevent satisfactory installation of the stone columns. Also, will only reduce



settlements by around 50% and there is much less certainty regarding performance compared with a piled solution.

6. Staged construction with preloading

For this option the construction sequence likely to be as follows:

- Install vertical band drains over embankment footprint
- Construct embankment to say 3m.
- Wait 3 months
- Construct embankment to say 6m
- Wait 3-6 months
- Excavate embankment within culvert footprint
- Build culvert structures
- Complete embankment to finished road level
- Wait 3-6 months
- Complete road pavement and drainage

This is likely a lot cheaper than options 2 to 4 and maintains the current earthworks balance. Drain spacings and sequence can be optimised to reduce programme time but overall it will take a lot longer to construct. There may also be some significant residual settlements of the culvert structures in the unload/reload periods.

7. Part Lightweight Fill embankment

Potential sequence as follows:

- Install vertical band drains over embankment footprint
- Construct embankment to say 3m (or 1m above flood level).
- Wait 6 months
- Reduce embankment height by 1m generally and to founding level within culvert footprint
- Build culvert structures
- Complete embankment to 1m below FRL using expanded polystyrene
- Complete road pavement and drainage

This is a bit better than option 6 in terms of programme but still slow. Material costs are high for expanded polystyrene fill and it will create a big surplus of fill material.

8. Viaduct Structure (constructed on piled foundations)

This option is included for completeness, but considering the cost and time penalties with other options, it is likely to be unfeasible. This option leaves a fill surplus but may help reduce impact on woodland. The viaduct structure however, will introduce a considerable maintenance liability for the asset manager.



Option 1 was selected as the preferred ground improvement solution and the current proposal includes piling the embankment directly affected by the proposed A59 alignment. It should be noted that the current embankment area identified for piling is a conservative estimate subject to being refined as the detail design progresses.

Following on from this, any solution choice for structures no.7 - 10 would require robust foundations mitigating against the likely effects of ground settlement i.e. piles. Due to their large size, a piped solution is considered unfeasible. A piled box or portal solution is viable with the latter preferred as this would provide a structurally efficient solution.

A precast concrete portal is not preferred as this would require a longitudinal joint along the top of the pilecap that would be difficult to access, inspect and maintain. In addition, insitu construction would allow for a corbel to be incorporated as part of the design to readily facilitate mammal access requirements. For this reason, an insitu concrete portal (option C) will piled foundations is the preferred solution for structure no. 7 - 10.

Structure no.12 is associated with low flows and is also located within the proposed piled embankment zone. Due to its small internal diameter, a precast concrete pipe (option D) appears to be the most practical solution. A type Z pipe bedding (concrete surround) in accordance with the DMRB Highway Construction Details is considered suitable for this location.

Refer to proposed structure general arrangement in Appendix C for further details.



Conclusion & Recommendation

Based on a high-level assessment and geotechnical information to date, it is recommended that consideration be given to the development of the following:


- Option A (Precast Concrete Box) for Structure no.1 & 5
- Option C (Insitu Concrete Portal) with piled foundations for Structure no. 7, 8, 9 & 10
- Option D (Precast Concrete Pipe) for Structure no. 11 & 12

Following initial discussions with NYCC, all 8no. culvert structures are to be classified as Category 1 in accordance with BD2/12 with requirement for Approval In Principles (AIP) and TAA approval. The following will also be required in order to progress to the detailed design stage:

- Confirmation of new culvert structure locations.
- Confirmation of existing statutory undertaker's services at culvert locations.
- Structural finish/fascia/cladding requirements to the headwall/wingwalls.
- Provision of any specific environmental features.
- Requirement for any additional hydraulic features (flow control mechanisms, scour protection, plunge pools etc.) to be installed to any of the structures.
- Any other additional site investigation information.
- Geotechnical design report (GDR).




APPENDIX A – STRUCTURE LOCATION PLAN





APPENDIX B – STRUCTURE OPTION SKETCHES



(. WIDTH (m)	APPROX. HEIGHT (m)			
) DIAMETER (PIF	CIRCULAR CONCRETE			
2100	1700			
METER CIRCU	LAR CONCRETE PIPE			
1000	1400			
3300	1950			
3900	2125			
900 x 900 S	TONE ARCH			
2100	2250			
4200	2550			
METER CIRCULAR CONCRETE PIPE				
METER CIRCU	LAR CONCRETE PIPE			

NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT STRUCTURES, EARTHWORKS AND ROADWORKS DRAWINGS. ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.
- ALL LEVELS, CHAINAGES AND SETTING OUT POINTS ARE IN
- ALL LEVELS, CHAINAGES AND SET HING ON POINTS ARE IN METERS UNLESS NOTED OTHERWISE. ALL FORMATION LEVELS TO BE CONFIRMED ON SITE. THE FORMATION SHALL BE CHECKED FOR THE PRESENCE OF SOFT OR LOOSE SPOTS AND REPLACED WITH ACCEPTABLE COMPACTED GRANULAR MATERIAL. CONSTRUCTION SEQUENCE TO BE DETERMINED AT DETAILED DESIGN STAGE.

P01	09/08/19	FOR INFORMATION	LS	IM	HM
Rev.	Date	Description	By	Chk'd	App'd



Three White Rose Office Park, Millshaw Park Lane, Leeds, LS11 0DL, UK T+ 44 (0) 113 395 6200, F+ 44 (0) 113 395 6201 wsp.com




A59 KEX GILL DIVERSION

CULVERT STRUCTURE FEASIBILITY **OPTION SKETCHES (SHEET 1 OF 2)**

Scale	Drawn	Checked	Approved	Authorised
AS SHOWN	L. Slinn	I.Mulla	H.Mistry	H.Mistry
Original Size	Date	Date	Date	Date
A1	09/08/19	09/08/19	09/08/19	09/08/19
Drawing Status	Suitability			
F	S1			
Drawing Number Project	Project Ref. No.			
70049554	Revision			
ALL	DR Type		01 nber	P01



APPENDIX C – PROPOSED GENERAL ARRANGEMENT



우. 0 SCALE DO NOT

P01

DR CB

ALL

0002

Appendix G

TAA CORRESPONDENCE

CONFIDENTIAL | WSP

1150

APPROVAL IN PRINCIPLE	Name of Project:	A59 Kex Gill Diversion
(Bridge and other Highway Structures)	Name of Bridge/Structure: Structure Ref. No.:	A59 Kex Gill Culvert (Structure no.5) STR005

AIP Comments Record Sheet

Scheme Name:	A59 Kex Gill Diversion	Comment Sheet Document Control			
Document Ref:	NYKGDD-WSP-SMN-STR005-RE-CB-0001	Comment Sheet Version	Date NYCC Comment Sent	Date Designer's Reply Sent	Notes
AIP Version:	P01	A B	16.10.2019 22.10.2019	18.10.2019	

AIP Submission Date: 03 October 2019

No.	AIP Section	Initial Comment (NYCC Response), and further comments on Designer's reply	Designer's Reply	Accepted by NYCC
1	Drawing	Scour, long fall is at a relatively high gradient. Consideration to scour protection at the downstream end is required.	Noted. Consideration shall be given to the provision of scour protection at the culvert downstream location in the form of a reno mattress (or similar).	Ok
2	Drawing	500dia drain outfall needs to be reviewed and check that there is no risk of scour, this should be at invert level rather than high up.	The drainage ditches at the upstream location of the culvert shall be re-aligned to feed into the culvert headwall with the wingwall splays adjusted to suit. This will negate the need for 500 dia. holes in the wingwalls.	Ok
3	3.5	Tok strip should be used at the precast box culvert joints rather than hydrophilic sealant	Noted. Section will be updated to replace hydrophilic sealant with Tok strip sealant.	Ok

APPROVAL IN PRINCIPLE	Name of Project:	A59 Kex Gill Diversion
(Bridge and other Highway Structures)	Name of Bridge/Structure: Structure Ref. No.:	A59 Kex Gill Culvert (Structure no.5) STR005

4	3.8	Parking for inspections is required on one side of the road, doesn't need to be formally surfaced	Noted. Section will be updated to include the following statements:	
			<u>Upstream Headwall Access</u> VRS on the proposed A59 eastbound carriageway terminates approximately 45m beyond the culvert headwall. The proposed verge width at this location is currently 2.5m. This can be locally widened to 3.5m to accommodate parking during inspections (in accordance with figure 7.10.1a of DMRB document CD169). Inspectors can then walk behind the VRS to reach the headwall (refer to sketch below). Can the TAA please confirm if this is acceptable?	
			Verge to be locally widened to 3.5m to allownstream Headwall Access	Ok
			Access to the downstream headwall (south) shall be permitted via the bridleway track.	

APPROVAL IN PRINCIPLE	Name of Project:	A59 Kex Gill Diversion
(Bridge and other Highway Structures)	Name of Bridge/Structure: Structure Ref. No.:	A59 Kex Gill Culvert (Structure no.5) STR005

AIP Comments Record Sheet

Scheme Name:	A59 Kex Gill Diversion	Comment Sheet Document Control			
Document Ref:	NYKGDD-WSP-SMN-STR005-RE-CB-0001	Comment Sheet Version	Date NYCC Comment Sent	Date Designer's Reply Sent	Notes
AIP Version:	P03	A	-	05/05/2023	Updates for value engineering

AIP Submission Date: 05/05/2023

No.	AIP Section	Initial Comment (NYCC Response), and further comments on Designer's reply	Designer's Reply	Accepted by NYCC
1	3.2		Changed:	
			"The wingwalls shall comprise freestanding <u>L-shaped</u> cantilever wall acting independent of the box culvert. "	
			То:	
			"The wingwalls shall comprise freestanding cantilever <u>type</u> wall <u>s</u> acting independent <u>ly</u> of the box culvert. "	
2	3.5		Deleted "creating a monolithic integral structure" at end of first sentence as it is misleading, the box culverts are interlocked but not monolithic.	
3	3.10.1		Table 1 – structural concrete. Added "Minimum strength" as most precast suppliers typically use higher classes than C40/50.	

APPROVAL IN PRINCIPLE	Name of Project:	A59 Kex Gill Diversion
(Bridge and other Highway Structures)	Name of Bridge/Structure: Structure Ref. No.:	A59 Kex Gill Culvert (Structure no.5) STR005

No.	AIP Section	Initial Comment (NYCC Response), and further comments on Designer's reply	Designer's Reply	Accepted by NYCC
4	3.10.1		Table 1 – blinding concrete.	
			Corrected type of concrete to "designated concrete in accordance with BS 8500-1:2015+A2:2019" rather than "prescribed standard concrete".	
5	3.10.1		Table 1 – waterproofing	
			Added "A permitted waterproofing system (in accordance with series 2000 of the MCHW) shall be used on the top outer surface of the box culverts and be continued down the outside of the abutment to a level 200 mm below the soffit."	
			Edited the second paragraph to read (edits underlined): -	
			"All structure <u>external</u> buried surfaces <u>(including the base) not</u> <u>protected by a permitted waterproofing system</u> shall be coated with two coats of bituminous paint (in accordance with series 2000 of MCHW) for below ground concrete structures."	
6	3.10.1		Table 1 – structural backfill	
			Added parameters that are in specification.	
			"Minimum effective angle of friction ϕ ' = 35°, and effective cohesion c' = 0."	
7	3.10.3		Table 3 – U4	
			Clarified which areas need U4 finish.	

APPROVAL IN PRINCIPLE	Name of Project:	A59 Kex Gill Diversion
(Bridge and other Highway Structures)	Name of Bridge/Structure: Structure Ref. No.:	A59 Kex Gill Culvert (Structure no.5) STR005

No.	AIP Section	Initial Comment (NYCC Response), and further comments on Designer's reply	Designer's Reply	Accepted by NYCC
8	3.10.4		References to back of wall drainage to culvert units has been removed, paragraph now reads: -	
			"Weepholes are to be provided to the wingwalls, with a filter medium placed directly behind them to prevent backfill material loss. This shall assist in relieving the build-up of pore water pressures."	
9	6		Section updated to reflect current information.	
10	9		Updated WSP signature panel.	
11	10		Added additional signature box for NYCC as requested.	
12	App A - TAS		Added "BS EN 14844:2006 (+A2:2011) Precast concrete products - Box culverts" to Section 4 Product Standards. This standard leads to the CE marking for box culverts. This is a 'harmonized' standard and fully encompasses the requirements of the Eurocodes.	
13	App C – GA DWG		Updated	



Three White Rose Office Park Millshaw Park Lane Leeds LS11 0DL

