



DO NOT SCALE

Legend:

- NYCC Highway Boundary
- Red Line Boundary
- Retained Trees
- Retained Ancient Veteran Trees
- Retained Woodland
- Retained Hedge
- G1 Highway Verge and Visibility Splay (Pollinator Mix-Mown to maintain height of 0.26)
- G2 Wildflower and Grass Meadow for Acid Soils
- G3 Upland Heathland/ Acid Grassland- Agricultural Pasture (Allow for 5% of Heather seed to be sourced via local landowner, the remaining to be sourced commercially due to quantity required)
- G4 Wet Grassland (Alongside Hall Beck watercourse and within Attenuation Pond. Allow areas to recolonise naturally. No seed mix necessary in these areas)
- G5 Wildflower and Grass Meadow Mix for Neutral Soils (Pollinator Mix)
- G6 Woodland Wildflower and Grass Mix
- Watercourse
- Open Water
- Timber Post and Rail Tree Guard
- Riverine Stone and Gravel
- W1 - Broadleaf Deciduous Woodland Mix
- W2 - Wet Woodland Mix
- W3 - Woodland Edge Mix
- W4 - Individual Tree (Extra Heavy)
- W5 - Individual Tree (Feathered)
- W6 - Scrub

- Notes:**
- All works within the NYCC Highway boundary to be the responsibility of the NYCC Highways Department from the end of the 5-year Establishment Period.
 - Areas of land outwith the NYCC Highways boundary will revert to the Landowner for ongoing maintenance.

NOTE - CONSTRUCTION ISSUE C03

- Amendments to the design at Church Hill (minor amendments to the boundary treatments to allow for the road reconfiguration, and gates altered at church car park);
- Amendments to the design at Hall Lane (minor amendments to the boundary treatments to allow for the road reconfiguration);
- Division of Hall Beck (alteration to watercourse alignment and design);
- Soft landscaping around drainage areas including Attenuation Ponds (refer to Point 6);
- Siting of interceptor channels and filter drains (soft landscaping around changes in Point 3);
- Variation in slope angle on certain sections (change in type of planting in certain areas due to underlying geotechnical feature placement associated with soil stability);
- Inclusion of reinstatement works for areas used as temporary construction compounds;
- Areas of woodland and scrub planting are to be reconfigured, following recent tree clearances; and
- No. 8 additional tree guards will be provided within livestock fields near Blubberhouses Hall to protect growing trees.

REV	DATE	BY	DESCRIPTION	CHK	APP
C03	21/08/2023	MM	FOR CONSTRUCTION	SF	AW
C02	24/03/2023	MM	CONTRACTORS STORAGE AREAS REVISED	SF	AW
C01	01/02/2023	MM	CONSTRUCTION ISSUE BASED ON HIGHWAY DESIGN VERSION JUNE 2021	SF	AW
T02	18/06/2020	CM	TENDER CONSULTATION EDITS	SF	AW
T01	26/11/2019	LA	FIRST ISSUE	SF	AW

DRAWING STATUS: **S3 - FOR REVIEW**

wsp

No 8 First Street, Manchester, M15 4RP, UK
T+44 (0) 161 200 5000
wsp.com

CLIENT: **North Yorkshire County Council**

ARCHITECT: **wsp**

SITE/PROJECT: **A59 KEX GILL DIVERSION**

TITLE: **Soft Landscape: Planting Plan (Sheet 13 of 15)**

SCALE @ A1: 1:500	CHECKED: SF	APPROVED: AW
PROJECT NO: 70049554	DESIGNED: SF	DATE: 21/08/2023
DRAWING NO: NYKGDD-WSP-ELS-SG-DR-LE-00023	REV: C03	

© WSP UK Ltd

File name: C:\USERS\MM\WORKSPACE\PROJECTS\NYCC\A59 KEX GILL DIVERSION\DRAWINGS\231023\2302\PLANTING PLAN_C03_STANDARD\PLANTING PLAN_C03_DRAWING.dwg, printed on 22 March 2024 13:32:12, by Mahira, Mihal

This drawing may contain: Ordnance Survey data © Crown copyright and database right 2023.